

**ENVIRONMENTAL COMPLIANCE APPROVAL  
For a Municipal Stormwater Management System**

**ECA Number: 078-S701**

**Issue Number: 1**

Pursuant to the *Environmental Protection Act*, R.S.O 1990, c. E. 19 (EPA), and the regulations made thereunder and subject to the limitations thereof, this environmental compliance approval is issued under section 20.3 of Part II.1 of the EPA to:

**Wilmot, The Corporation of the Township of**

**60 Snyder's Road West  
Baden, Ontario, Ontario N3A 1A1**

For the following Sewage Works:

**Township of Wilmot Stormwater Management System**

This Environmental Compliance Approval (ECA) includes the following:

<b>Schedule</b>	<b>Description</b>
Schedule A	System Information
Schedule B	Municipal Stormwater Management System Description
Schedule C	List of Notices of Amendment to this ECA: Additional Approved Works
Schedule D	General
Schedule E	Operating Conditions
Schedule F	Residue Management
Appendix A	Stormwater Management Criteria

Except where specified otherwise, all prior ECAs, or portions thereof, issued by the Director for Sewage Works described in section 1 of Schedule B are revoked and replaced by this Approval.

DATED at TORONTO this 8th day of February, 2023

Signature



Aziz Ahmed, P.Eng.  
Director, Part II.1, *Environmental Protection Act*

## Schedule A: System Information

System Owner	<b>Wilmot, The Corporation of the Township of</b>
ECA Number	<b>078-S701</b>
System Name	<b>Township of Wilmot Stormwater Management System</b>
ECA Issue Date	<b>February 8th, 2023</b>

### 1.0 ECA Information and Mandatory Review Date

ECA Issue Date	February 8th, 2023
Application for ECA Review Due Date	August 15, 2027

1.1 Pursuant to section 20.12 of the EPA, the Owner shall submit an application for review of the Approval no later than the Application for ECA Review Date indicated above.

### 2.0 Related Documents

#### 2.1 Other Documents

Document Title	Version
Design Criteria for Sanitary Sewers, Storm Sewers, and Force mains for Alterations Authorized under Environmental Compliance Approval	v.1.2 (Jan 23, 2022)

### 3.0 Stormwater Master Plan and Asset Management Plan

Document Title	Version
Asset Management Plan – Storm Infrastructure	v.1(2022)
Alder Creek Watershed Study and Upper Strasburg Creek Subwatershed Study	v.1(January 2008)

### 4.0 Operating Authority

System	Operating Authority
Stormwater Management System	The Corporation of the Township of Wilmot

## Schedule B: Municipal Stormwater Management System Description

System Owner	Wilmot, The Corporation of the Township of
ECA Number	078-S701
System Name	Township of Wilmot Stormwater Management System
ECA Issue Date	February 8th, 2023

### 1.0 System Description

- 1.1 The following is a summary description of the Sewage Works comprising the Municipal Stormwater Management System:

#### Overview

The Municipal Stormwater Management (SWM) System serving the Township of Wilmot's drainage area, is a separate system for stormwater (i.e. designed not to convey sanitary sewage, combined sewage) within local Wilmot watersheds. The Municipal SWM System consists of storm sewers, culverts, ditches, Stormwater Management Facilities and outlets.

This ECA covers the entire Municipal SWM System owned and operated by the Township of Wilmot. This ECA does not cover municipal drains, municipally or privately owned sewage works on industrial or commercial land.

#### Sewage Collection System

- 1.2 The Authorized System comprises:
- 1.2.1 The Sewage Works described and depicted in each document or file identified in column 1 of Table B1.

Table B1: Infrastructure Map	
Column 1 Document or File Name	Column 2 Date
Storm Sewer BADEN	May 2022
Storm Sewer MANNHEIM	May 2022
Storm Sewer NEW DUNDEE	May 2022
Storm Sewer NEW HAMBURG	May 2022
Storm Sewer PETERSBURG	May 2022

Storm Sewer ST. AGATHA	May 2022
------------------------	----------

- 1.2.2 Storm Sewers, Stormwater Management Facilities, stormwater pumping stations and Sewage Works associated with a Third Pipe Collection System that have been added, modified, replaced, or extended through authorization provided in a Schedule C Notice respecting this Approval, where Completion occurs on or after the date identified in column 2 of Table B1 for each document or file identified in column 1.
- 1.2.3 Storm Sewers, Stormwater Management Facilities and Sewage Works associated with a Third Pipe Collection System that have been added, modified, replaced, or extended through authorization provided by Schedule D of this Approval, where Completion occurs on or after the date identified in column 2 of Table B1 for each document or file identified in column 1.
- 1.2.4 Any Sewage Works described in conditions 1.3 through 1.8 below.

### Stormwater Collection System

- 1.3 Categorization of the Authorized System at the date of issue of this Approval is as follows:

System Type	Pipe Diameter (mm)	Length (km)	System Totals (km)
Storm Sewers	Up to 250	5.1	--
Storm Sewers	> 250 - 500	36.8	--
Storm Sewers	> 500 - 1050	20.7	--
Storm Sewers	> 1050	2.3	--
Total Storm Sewers	--	--	64.9
Ditches / Swales	--	--	3.1
Total System Length (km)	--	--	68

Facility Type	Basic Treatment for Suspended Solids*	Normal Treatment for Suspended Solids *	Enhanced Treatment for Suspended Solids *	Other Treatment Level for Suspended Solids**	Total Quality Control	Total Quantity Control	Total Number of Facilities
LID Facilities - Retention (infiltration, evapotranspiration, harvest)	--	--	--	--	--	--	0
LID Facilities -	--	--	--	--	--	--	0

Filtration							
Stormwater Management Ponds – Wet (includes wetlands, hybrids)	21	3	2	--	26	26	26
Stormwater Management Ponds - Dry	3	--	--	--	--	--	3
Super Pipe / Storage Facility	--	--	--	--	--	--	0
Filtration MTD - Filter Unit	--	--	--	--	--	--	0
Sedimentation MTD - OGS	1	3	--	--	4	--	4
Pumping Stations	--	--	--	--	--	--	0
Other	--	--	--	--	--	--	0
Total Number of Facilities	--	--	--	--	30	26	33

\* Basic, normal, and enhanced treatment correspond to 60%, 70% and 80% suspended solids removal on an annual average long-term basis, respectively.

\*\* Treatment levels below 60% suspended solids removal on an annual average long-term basis.

**Table B4. Third Pipe Collection System**

Description	Pipe Diameter (mm)	Length (km)	Quantity	System Totals
Third Pipe Sewer	Up to 250	--	N/A	--
Third Pipe Sewer	> 250 - 500	--	N/A	--
Third Pipe Sewer	> 500	--	N/A	--
Total	--	--	--	Km
Other Infrastructure Components (e.g., storage tank)	N/A	N/A	--	--

**Table B5. Sewage Works on Private Land that are part of the Municipal Stormwater Treatment Train\***

Description	Location	ECA # (if applicable)	
N/A	N/A	N/A	N/A

\* Identifies privately owned Sewage Works that are not part of the Authorized System, but are part of a Stormwater Treatment Train

### Stormwater Management Facilities

1.4 The following are Stormwater Management Facilities in the Authorized System:

**Asset ID STWMF20 – Activa Baden Stormwater Management Facility – Wetland**

Location	Activa Baden Subdivision, Part of Lots 14 and 15, North of Snyder's Road
Watershed/Subwatershed	Tributary of Baden Creek
Receiver of discharge	To discharge to a tributary of Baden Creek via the existing CNR culvert into the Baden Creek: including all appurtenances.
Outlet location	43.404903, -80.668421
Catchment Area	52.78 ha
Level of Treatment for suspended solids	70-80% efficiency including overflow weirs and discharge facilities
Treatment for other contaminants, as required	N/A
Level of Volume control	Constructed wetland with approximate volumes of 2,416 m <sup>3</sup> in permanent, 2,111 m <sup>3</sup> for extended detention and 19,145 m <sup>3</sup> in total storage capacity
Design Storm	Flow characteristics of Wetland and area berm: Pre-development peak flows (cu.m/s) 25mm storm – 0.61 m <sup>3</sup> /s 2-year storm – 1.37 m <sup>3</sup> /s 5-year storm – 2.87 m <sup>3</sup> /s 100-year storm – 3.67 m <sup>3</sup> /s Attenuating post-development peak flows from wetland (cu.m/s) 25mm storm – 0.17 m <sup>3</sup> /s 2-year storm – 0.37 m <sup>3</sup> /s 5-year storm – 1.37 m <sup>3</sup> /s 100-year storm – 7.45 m <sup>3</sup> /s Post-development peak flows (m <sup>3</sup> /s) from the site 25mm storm – 0.42 m <sup>3</sup> /s 2-year storm – 0.95 m <sup>3</sup> /s 5-year storm – 2.19 m <sup>3</sup> /s 100-year storm – 3.17 m <sup>3</sup> /s
Reference ECA(s)	ECA Number 1790-53FQK8
Reference Works as part of treatment train	N/A
Brief Description	Constructed wetland with one (1) forebay area with an overflow weir, one (1) 1,500mm diameter perforated outlet riser, complete with 200mm and 375mm outlet orifices, one (1) 2,400mm diameter ditch inlet catchbasin/manhole, two (2) 600mm diameter outlet pipes, lowflow cooling trench, 2.4m wide rip-rap outlet channel, headwall, 30m wide overflow/emergency weir berm, extended flood plain. Flood control property berm, 1,600mm by 800mm bottomless culvert. Two (2) 1.83m diameter oil and grit separators, each having a flow capacity of 18 L/s at efficiency 70-80% including overflow weirs and discharge facilities.

Receive Emergency Sanitary Overflows	No
Notes / Additional Information	N/A

**Asset ID STWMF15 & STWMF18 – Baden East Stormwater Management Facility - Wetland & Detention Pond**

Location	Baden East Subdivision, Part of Lots 13 and 14, Wilmot Township
Watershed/Subwatershed	Tributary of Baden Creek
Receiver of discharge	Pond #2 (STWMF18) - Discharging through a 150 mm diameter pipe into the Baden Creek, and a 30 meter wide overflow weir (elevation of 351.35 meters) Pond #3 (STWMF15) - Discharging through a 250 mm diameter pipe ultimately into Baden Creek, and eight meter wide overflow weir (elevation 356.4 meters)
Outlet location	43.401607, -80.656919
Catchment Area	12.3 ha
Level of Treatment for suspended solids	Designed to provide at least 74.8 % Total Suspended Solids Removal, located upstream of Pond # 3 on John Henry Stiefelmeyer Crescent
Treatment for other contaminants, as required	N/A
Level of Volume control	Pond #2 is a constructed wet pond with approximate volumes of 544 m <sup>3</sup> in permanent, 427 m <sup>3</sup> for extended detention and 2,247 m <sup>3</sup> in total storage capacity  Pond #3 is a constructed wetland with approximate volumes of 146 m <sup>3</sup> in permanent, 95 m <sup>3</sup> for extended detention and 895 m <sup>3</sup> in total storage capacity
Design Storm	Designed to attenuate post-development flow levels below the pre-development flow levels from storm events with up to 1:100 years return frequency
Reference ECA(s)	ECA number 4289-52FPYE
Reference Works as part of treatment train	N/A
Brief Description OGS:	Pond #3 - One (1) precast concrete oil and grit separator with an inside diameter of 1.83 meters and a maximum treatment capacity of 18 L/sec (STC 750 Model), designed to provide at least 74.8 % Total Suspended Solids Removal, located upstream of Pond # 3 on John Henry Stiefelmeyer Crescent
Brief Description:	Pond #2 - Constructed wetland to provide stormwater quality and quantity control for a 10.2 ha drainage area, located in the southeast corner of the subdivision, having a permanent pool storage capacity of 377 m <sup>3</sup> , extended detention storage capacity of 478 m <sup>3</sup> , and total storage capacity of 2,520 m <sup>3</sup> at an elevation of 351.55 meters, equipped with a 1.5 meters deep forebay, two (2) low flow channels, an outlet micro-pool, and an outlet structure consisting of a 75 mm diameter vertical orifice plate



---

	(elevation of 350.50 meters) and a 75 mm diameter horizontal orifice plate (elevation 350.80 meters) Pond #3 - One (1) dry detention pond to provide stormwater quantity control for a 1.74 ha drainage area, located at the northeast corner of the subdivision, having a total storage capacity of 406 m <sup>3</sup> at an elevation of 356.70 meters, equipped with an outlet structure consisting of a 135 mm diameter vertical orifice (elevation 355.76 meters) placed inside a rip rap protective layer
Receive Emergency Sanitary Overflows	No
Notes / Additional Information	N/A

**Asset ID STWMF26 – Baden West Stormwater Management Facility – Wet Pond**

Location	Baden West Subdivision, Part of Lot 16 located on Block 122, South of Snyder's Road, Township of Wilmot
Watershed/Subwatershed	Tributary of Baden Creek
Receiver of discharge	Discharging to a 1200 mm diameter manhole discharging via a 250 mm diameter outlet pipe to the outlet headwall, together allowing a maximum discharge of 1.72 m <sup>3</sup> /s (100-year storm event) to the existing unnamed tributary of Baden Creek
Outlet location	43.400024, -80.675152
Catchment Area	10.24 ha within the proposed development and conveying and providing limited peak flow quantity control for runoff from an external area of 34.25 ha.
Level of Treatment for suspended solids	Assumed Level 1, 60%, TSS removal
Treatment for other contaminants, as required	Emergency overflow sanitary discharge from the Charlotta Pump Station discharges into the pond
Level of Volume control	Having a permanent storage volume of 3,430 m <sup>3</sup> , an extended detention storage volume of 1,272 m <sup>3</sup> , and a total active storage volume of 20,879 m <sup>3</sup>
Design Storm	Collecting and providing quality control and peak flow quantity control for all events up to 1:100-year return-period.
Reference ECA(s)	ECA number 6069-6A9LYK
Reference Works as part of treatment train	N/A
Brief Description:	Complete with two (2) inlet structures including a 1200 mm diameter inflow pipe and headwall and a 750 mm diameter inflow pipe and headwall, sediment forebay, permanent pool, a 0.9 m wide trapezoidal emergency overflow spillway with 10:1 side slopes provided for events greater than the 100-year storm event and outlet structure consisting of a 1.8 m perforated CSP riser housing a 120 mm diameter orifice plate directing up to 0.053 m <sup>3</sup> /s (maximum pond elevation) to an outlet cooling trench, a 150 mm diameter orifice plate and a 600 mm diameter orifice, a 900 mm diameter outlet pipe, an 800 mm by 1260 mm diameter horizontal elliptical outlet pipe and a 2.4 m diameter control manhole housing an 850 mm diameter orifice plate, a 1200 mm diameter outlet pipe, outlet headwall, the 2 m wide, 1 m deep and 20 m long outlet cooling trench filled with clear stone and wrapped with geotextile filter fabric consists of one (1) 250 mm diameter perforated inlet pipe plugged at the downstream end and one (1) 250 mm diameter perforated outlet pipe
Receive Emergency Sanitary	Yes

Overflows	
Notes / Additional Information	Sanitary overflow for Charlotta pump station. Lift station 4

**Asset ID STWMF24 – Crescendo Stormwater Management Facility – Wet Pond**

Location	Crescendo Subdivision located north of Regional Road No.
----------	--

	6, Township of Wilmot
Watershed/Subwatershed	Tributary of Baden Creek
Receiver of discharge	Baden Creek
Outlet location	43.401149, -80.659533
Catchment Area	Total contributing drainage area of 102.15 ha
Level of Treatment for suspended solids	Assumed Level 1, 60% TSS removal
Treatment for other contaminants, as required	N/A
Level of Volume control	The pond having a permanent storage volume of 260 m <sup>3</sup> , an extended storage volume of 480 m <sup>3</sup> , and an available storage volume of 1075 m <sup>3</sup> at a water depth of 1.0m and corresponding elevation of 347.1m
Design Storm	To control the post development peak discharge rates from the 1:5 year, 1:25 year and 1:100 year design storms to within pre-development peak discharge levels of 0.75 m <sup>3</sup> /s and 6.81 m <sup>3</sup> /s, respectively
Reference ECA(s)	ECA number 3-0453-98-006
Reference Works as part of treatment train	N/A
Brief Description:	Available storage volume of 1075 m <sup>3</sup> at a water depth of 1.0m and corresponding elevation of 347.1m, with a diversion chamber, inlet and outlet control structures and sedimentation chamber, outletting to the existing storm detention pond to control the post development peak discharge rates from the 1:5 year, 1:25 year and 1:100 year design storms to within pre-development peak discharge levels of 0.75 m <sup>3</sup> /s and 6.81 m <sup>3</sup> /s respectively.
Receive Emergency Sanitary Overflows	No
Notes / Additional Information	Includes approximately 158m of storm sewers ranging in diameter from 375mm to 825mm, catchbasins, catchbasin manholes and associated piping and appurtenances.

**Asset ID STWMF2 – Edgehill Estates Stormwater Management Facility – Detention Pond**

Location	Edgehill Estates Subdivision, St. Agatha Heights, Township
----------	--

	of Wilmot located approximately 400m northwest of Wilma Street and St. Anne Avenue.
Watershed/Subwatershed	Nith River
Receiver of discharge	The west of the site outlets through a pronounced swale to a culvert crossing Regional Rd 9, approximately 1350m west of Regional Rd 12. This swale connects to a creek on the south side of Regional Rd 9 and eventually into the Nith River.
Outlet location	43.436539, -80.639610
Catchment Area	22 ha
Level of Treatment for suspended solids	Assumed Level 1, 60% TSS removal
Treatment for other contaminants, as required	N/A
Level of Volume control	A permanent pool of 60 m <sup>3</sup> , an extended retention volume of 750 m <sup>3</sup> and a total storage volume of 2,600 m <sup>3</sup> (100-year).
Design Storm	A berm has been constructed to store a complete 100-year post development storm and will gradually discharge at the controlled 5-year predevelopment rate.
Reference ECA(s)	ECA number 3-1299-85-006
Reference Works as part of treatment train	N/A
Brief Description:	It will consist of a berm constructed across the present swale and built to a height of 2m. A 525mm diameter culvert will be placed at a height of 0.5m from the base so that the detention facility will also act temporarily as a silt basin. The culvert will be designed to carry only the 5-year predevelopment flow to match existing. Some stone treatment to be constructed at the outlet of the pipe to prevent erosion.
Receive Emergency Sanitary Overflows	No
Notes / Additional Information	Discharges into farmers field

### Asset ID STWMF13 – Fairview Heights Stormwater Management Facility – Retention Pond

Location	Fairview Heights Subdivision, Township of Wilmot located at the north-east corner of the subdivision
Watershed/Subwatershed	Nith River

Receiver of discharge	575mm diameter pipe transports storm runoff to an easement and then into the Nith River.
Outlet location	43.371638, -80.704602
Catchment Area	4.5 ha
Level of Treatment for suspended solids	Assumed Level 1, 60% TSS removal
Treatment for other contaminants, as required	N/A
Level of Volume control	Constructed detention pond with 296 m <sup>3</sup> in total storage capacity
Design Storm	Design flows (m <sup>3</sup> /s) for 5-year and 100-year storms Peak pre-development – 0.048 m <sup>3</sup> /s 5-year storm Peak post-development – 0.151 m <sup>3</sup> /s 5-year storm Attenuated discharge – 0.038 m <sup>3</sup> /s 5-year storm Peak pre-development – 0.211 m <sup>3</sup> /s 100-year storm Peak post-development – 0.408 m <sup>3</sup> /s 100-year storm Attenuated discharge – 0.217 m <sup>3</sup> /s 100-year storm
Reference ECA(s)	ECA number 3-0102-93-006
Reference Works as part of treatment train	N/A
Brief Description:	Stormwater retention pond with a storage capacity of approximately 513 m <sup>3</sup> , with outlet control facility to restrict the flow into the existing roadside ditch along Highway 7 & 8. Approximately 33m of 1500mm diameter oversized pipe located between CBMH No. 8 and MH No.4 on Joseph Street to provide 55m <sup>3</sup> storage volume and an orifice in MH No. 4 to attenuate the 5-year design storm flow from 0.039 m <sup>3</sup> /s to 0.020 m <sup>3</sup> /s in the existing storm sewer at the site.
Receive Emergency Sanitary Overflows	No
Notes / Additional Information	Discharge into MTO ditch

### Asset ID STWMF19 – Forrest Glen Stormwater Management Facility – Wet Pond

Location	Block 91 of the Glen Forest Subdivision, on Part 3, Township of Wilmot
Watershed/Subwatershed	Flood plain of Nith River
Receiver of discharge	Discharging to the Ivan-Gingerich Drain

Outlet location	43.393331, -80.707943
Catchment Area	Runoff from an area of 39 ha
Level of Treatment for suspended solids	Assumed Level 2, 70% TSS removal
Treatment for other contaminants, as required	Emergency overflow from the Forest Glenn Pump Station discharges into the SWMF
Level of Volume control	Constructed wet pond with approximate volumes of 415 m <sup>3</sup> in permanent, 1,973 m <sup>3</sup> for extended detention and 4,210 m <sup>3</sup> in total storage capacity
Design Storm	Stormwater management system collecting up to 100-year storm event
Reference ECA(s)	ECA number 0631-4W5NA2
Reference Works as part of treatment train	N/A
Brief Description:	Complete with inlet pipe, rip rap, forebay, overflow weir and outlet structure including a 100mm diameter orifice and a 215mm diameter orifice allowing a maximum discharge of 1.22 m <sup>3</sup> /s to the new 375mm diameter culvert under Regional Road No. 1 leading to the Ivan-Gingerich Drain
Receive Emergency Sanitary Overflows	No
Notes / Additional Information	Discharges into culvert under Regional Rd then into creek

#### Asset ID STWMF8 – Forrest Meadows Stormwater Management Facility – Detention Pond

Location	Forest Meadow Subdivision, New Hamburg, Township of Wilmot northeast of the intersection of Regional Road One (Waterloo Street) and William Street.
Watershed/Subwatershed	Nith River
Receiver of discharge	Discharge to the Grant Street storm sewer, the sewer drains in a westerly direction to the Nith River. Overland flows also flow to the Nith River.
Outlet location	43.386869, -80.713640

Catchment Area	8.6 ha
Level of Treatment for suspended solids	Assumed Level 1, 60% TSS removal
Treatment for other contaminants, as required	N/A
Level of Volume control	Estimated storage volume – 1497 m <sup>3</sup> for 5-year, 4835 m <sup>3</sup> for 100-year active storage volume
Design Storm	Runoff from 5-year and 100-year rainfall events as follows: Peak predevelopment flow – 1.75 m <sup>3</sup> /s 5-year Peak post development flow – 2.69 m <sup>3</sup> /s 5-year Peak-Post development flow (with control) – 1.74 m <sup>3</sup> /s 5-year Peak predevelopment flow – 6.89 m <sup>3</sup> /s 100-year Peak post development flow – 7.59 m <sup>3</sup> /s 100-year Peak-Post development flow (with control) – 6.22 m <sup>3</sup> /s 100-year
Reference ECA(s)	ECA number 3-1394-89-006
Reference Works as part of treatment train	N/A
Brief Description:	Missing information
Receive Emergency Sanitary Overflows	No
Notes / Additional Information	N/A

#### Asset ID STWMF22 – Kenneth Fried Stormwater Management Facility - Wetland

Location	Kenneth Fried Place, Township of Wilmot
Watershed/Subwatershed	Alder Creek floodplain/watershed
Receiver of discharge	Discharging via sheet flow to the existing wetland, eventually to Alder Creek via, together with temporary sediment and erosion control measures.
Outlet location	43.347499, -80.530601
Catchment Area	1.36 ha
Level of Treatment for suspended solids	Level 1 81.9% total suspended solids removal with an annual flow capture of 96%
Treatment for other	N/A



contaminants, as required	
Level of Volume control	Unknown
Design Storm	Quantity: 100-year storm with Level 1 Quality control (80% TSS Removal)
Reference ECA(s)	ECA number 2219-5J2UQY
Reference Works as part of treatment train	N/A
Brief Description OGS:	Installation of a STC 2000 manhole oil/grit separator with a maximum treatment capacity of 30 L/s and a total handling capacity of 10,925 L, immediately downstream of catchbasin/manhole CBMH5.
Brief Description of each component of treatment train:	A 525mm diameter storm sewer and an outlet structure comprising of a spreader berm made up of a perforated a 20m long, 400mm diameter pipe laid within a clear stone surround all encased in a filter fabric, overlaid with 300mm deep rip rap, complete with an emergency overflow structure.
Receive Emergency Sanitary Overflows	No
Notes / Additional Information	N/A

**Asset ID STWMF28 – MAK Subdivision Stormwater Management Facility – South Wet Pond**

Location	Mak Subdivision, Part of Lot 22, located on Block 200, in the southeast corner of the intersection of Conestoga Road and Forest Avenue, Township of Wilmot
Watershed/Subwatershed	Nith River
Receiver of discharge	Nith River
Outlet location	43.390999, -80.720327
Catchment Area	8.25 ha
Level of Treatment for suspended solids	Assumed Level 1, 60% TSS removal
Treatment for other contaminants, as required	N/A
Level of Volume control	Permanent storage volume of 296 m <sup>3</sup> , an extended storage

	volume of 330 m <sup>3</sup> , and a total storage volume of 3,584 m <sup>3</sup>
Design Storm	Quantity: 25mm rainfall, 5-year storm, 100-year storm; Quality: sediment forebay based on peak flow from 25mm storm event
Reference ECA(s)	ECA number 5297-68USPB
Reference Works as part of treatment train	N/A
Brief Description:	One (1) 900mm diameter inlet sewer, headwall, gabion mats, sediment forebay, permanent pool, overflow weir and outlet structure including a 1.2m perforated riser complete with a 125mm diameter orifice and a 300mm diameter orifice allowing a maximum discharge of 0.52 m <sup>3</sup> /s via a 375mm diameter outlet pipe and overflow structure to the existing storm catchbasin manhole CBMH66
Receive Emergency Sanitary Overflows	No
Notes / Additional Information	N/A

**Asset ID STWMM16 & STWMM17 – Mannheim Village Stormwater Management Facility – Wetlands, Infiltration Gallery and Soakaway Pits**

Location	Mannheim Village Estates (north of Ottawa Street and west of Trussler Road/Regional Road 70) in Mannheim Millennium Park Estates subdivision/residential development – Phase 2
Watershed/Subwatershed	Alder Creek watershed
Receiver of discharge	Soakaway Pits discharging to subsurface.

	<p>Eastern Stormwater Management Basin (STWMF16) discharging southerly to the existing storm sewer on an easement and excess flows will be discharged westerly via an emergency overflow towards Mannheim Crescent.</p> <p>Westerly Stormwater Management Basin (STWMF17) discharging easterly to the infiltration gallery on the site and excess flows will be discharged westerly via an emergency overflow/pathway towards Alder Creek.</p> <p>Infiltration Gallery infiltrating to subsurface and discharging an excess runoff to the existing storm sewer on Mannheim Crescent.</p> <p>Subdrain discharging westerly to a swale and existing ground towards Alder Creek.</p>
Outlet location	STWMF16 43.400363, -80.542144 STWMF17 43.399733, -80.545771
Catchment Area	26 ha
Level of Treatment for suspended solids	Assumed Level 1, 60% TSS removal
Treatment for other contaminants, as required	Emergency overflow from the Mannheim Sewage Pumping Station discharges on the road then overland into the pond.
Level of Volume control	<p>Eastern Stormwater Management Basin Quality control is provided by a permanent pool with an available volume capacity of approximately 1,399 m<sup>3</sup> and extended detention with an available storage volume of approximately 454 m<sup>3</sup>, a peak release rate of approximately 0.0105 cubic meters per second and an extended detention time of approximately 25.2 hours.</p> <p>Westerly Stormwater Management Basin Quality control is provided by a permanent pool with an available volume capacity of approximately 323 m<sup>3</sup> and extended detention with an available storage volume of approximately 500 m<sup>3</sup>, a peak release rate of approximately 0.010 m<sup>3</sup>/s and an extended detention time of approximately 24.8 hours.</p>
Design Storm	<p>Eastern Stormwater Management Basin Quantity control is designed for a range of design events including the 5 year and 100 year storms, available active storage volumes of approximately 7,780 and 10,700 cubic meters, respectively, and peak release rates of approximately 0.21 and 0.25 m<sup>3</sup>/s, respectively.</p> <p>Westerly Stormwater Management Basin Quantity control is designed for a range of design events including the 5 year and 100 year storms, available active storage volumes of approximately 2,265 and 3,440 m<sup>3</sup>, respectively, and peak release rates of approximately 0.21 and 0.56 m<sup>3</sup>/s, respectively.</p>
Reference ECA(s)	ECA number 1846-4YQS96
Reference Works as part of	N/A

treatment train	
Brief Description:	<p>Soakaway Pits (located on site / individual lots near boulevard property lines), designed as lot-level infiltration facilities (based on approximately 50 lots &amp; some parking areas, where applicable) each including a 100-millimeter diameter perforated pipe in an infiltration pit (a total volume of approximately 21.56 m<sup>3</sup>).</p> <p>Eastern Stormwater Management Basin (located within Block 71), designed as a constructed wetland facility with extended detention including an inlet structure (an inlet conduit with headwall). a deeper forebay micro pool within a main basin including a flow diversion berm &amp; a defined undulating low flowpath, and two (2) outlet structures (southerly - a perforated riser with the 125 &amp; 280 millimeter diameter orifice plates &amp; an overflow riser with outlet pipe to outlet manhole structure connected to the existing storm sewer; and westerly - an emergency overflow weir with channel / swale, within Block 68, to surface drainage pathways / Mannheim Crescent). The basin is designed for water quality and quantity control functions including a low flow augmentation and peak flow attenuation to pre-development levels for the total contributing area of approximately 46 hectares (with approximately 11.36 hectares of the development for water quality control).</p> <p>Westerly Stormwater Management Basin (located within Block 70), designed as a constructed wetland facility with extended detention including inlet conduits &amp; inlet structure, a deeper forebay micro pool within a main basin including a flow diversion berm &amp; a defined undulating low flow path, and two (2) outlet structures (easterly - a perforated riser with the 100 &amp; 450 millimeter diameter orifice plates &amp; an overflow riser with outlet pipe to outlet manhole structure connected to an infiltration gallery; and westerly an emergency overflow weir). The basin is designed for water quality and quantity control functions including a low flow augmentation and peak flow attenuation to pre-development levels for the total development contributing area of approximately 12.5 hectares.</p> <p>Infiltration Gallery (located easterly within Block 70, between Westerly Facility and Mannheim Crescent), designed as the end-of-pipe infiltration facility including an inlet manhole structure, a storm sewer conveyance conduit complete with two 300 millimeter diameter perforated subdrains installed in a 75 meter long infiltration trench and outlet manhole structure connected to the existing storm sewer (to Mannheim Estates - Phase I Subdivision). The facility receives controlled discharges from the Westerly Facility and will provide for water quantity control functions by a total storage capacity of approximately 2,145 cubic meters</p> <p>Subdrain (located within Block 70, along southerly and</p>

	westerly property limits), designed for quantity control by draining an excess subsurface water via a 300 millimeter diameter perforated pipe in an exfiltration trench.
Receive Emergency Sanitary Overflows	STWMF17 receives sanitary overflow
Notes / Additional Information	N/A

#### Asset ID STWMF6 – Meadowpark Stormwater Management Facility – Detention Pond

Location	Simon Wood Estates Phase II, part of Lots 1 and 2, south of Bleams Road in the Village of Mannheim, Township of Wilmot
Watershed/Subwatershed	Alder Creek
Receiver of discharge	Any flows coming from the pond will have to travel through two culverts and under Mannheim Road prior to outletting to Alder Creek.
Outlet location	43.393954, -80.542975
Catchment Area	27 ha
Level of Treatment for suspended solids	Assumed Level 1, 60% TSS removal

Treatment for other contaminants, as required	N/A
Level of Volume control	A permanent pool of 1482 m <sup>3</sup> , an extended retention volume of 4,150 m <sup>3</sup> (5-year) and a total storage volume of 6,117 m <sup>3</sup> (100-year).
Design Storm	The 5 year and 100 year design storm hyetographs were derived from Intensity- Duration-Frequency curves of the City of Kitchener using the Chicago method of rainfall distribution.
Reference ECA(s)	ECA number 3-1340-89-006
Reference Works as part of treatment train	N/A
Brief Description:	A 300mm diameter inlet pipe fitted with a 230mm diameter opening orifice plate for control of 5-year design peak flow. With 500mm diameter outlet pipe fitted with a 400mm diameter orifice plate for control of 100-year design peak flow with an emergency overflow weir.
Receive Emergency Sanitary Overflows	No
Notes / Additional Information	N/A

#### Asset ID STWMF9 & STWMF10 – New Dundee Heights Stormwater Management Facility – Wet Ponds

Location	Pond #1 (STWMF9) located on easement, between Bridge Street and Kurt Place on West side of Lots 11 and 12, Village of Dundee Pond #2 (STWMF10) located on Block 19, east of Lot 18, Village of Dundee
Watershed/Subwatershed	Alder Creek watershed
Receiver of discharge	The discharge from SWM Pond 1 is controlled by a combination of rock berm, orifice flow and weir flow through an earthfill berm structure. The runoff from this development eventually discharges into Alder Creek.
Outlet location	Pond #1 43.349081, -80.537688 Pond #2 43.348747, -80.538738
Catchment Area	22.59 ha
Level of Treatment for suspended solids	Assumed Level 1, 60% TSS removal
Treatment for other	N/A

contaminants, as required	
Level of Volume control	<p>Pond 1 2-year flood extended retention volume of 261 m<sup>3</sup> and an active storage volume of 533 m<sup>3</sup>.</p> <p>Pond 2 has a 2-year extended retention volume of 370 m<sup>3</sup> and an active storage volume of 3148 m<sup>3</sup>.</p>
Design Storm	<p>The stormwater management facilities are designed to control post-development runoff peaks to pre-development levels for the 5-year and 100-year storms. Design storms are created using the Chicago Method and the City of Kitchener IDF curves.</p> <p>Pond 1 has been designed to temporarily retain the pre-development runoff volumes from the 2-year storm event for lands upstream of Pond #1. The 2-year flows will be controlled by a rock berm to elevation 330.300m, at which point the water will overflow the berm and discharge through the outlet pipe.</p> <p>Pond 2 has been designed to temporarily retain the post-development runoff volumes from the 2-year storm event from the proposed subdivision. The 2-year flows will accumulate to an elevation of 322.900m, at which point the water will discharge through a Ditch Inlet Catchbasin Manhole structure. The 100-year flows will discharge into an existing Catchbasin Inlet Grate located on Bridge Street just south of the property.</p> <p>It is assumed that quality control measures for any future upstream development will be accommodated, in future plans.</p>
Reference ECA(s)	ECA number 3-1875-90-917
Reference Works as part of treatment train	N/A
Brief Description:	In both ponds, Regional storm flows will overtop the control structures and drain onto Bridge Street without flooding existing or proposed buildings.
Receive Emergency Sanitary Overflows	No
Notes / Additional Information	The ditch between Ponds #1 and #2 is proposed to be lined with riprap and filter cloth to act as additional water quality and erosion control from site runoff. This ditch cross-section will have the capacity for the 100-year post-development storm flows within a depth of 0.60m. The rip rap lining will encase the 5-year flows while the sodded embankments will encase the 100-year flows.

**Asset ID STWMF29 – Nithview Heights Stormwater Management Facility – Wetland**

Location	Nithview Heights Subdivision (Activa) Part of Lot 5, Township of Wilmot
Watershed/Subwatershed	Nith River Watershed
Receiver of discharge	Nith river
Outlet location	43.382750, -80.700365
Catchment Area	6.11 ha
Level of Treatment for suspended solids	Level 1 80% total suspended solids removal
Treatment for other contaminants, as required	N/A
Level of Volume control	A main cell consisting of 317 m <sup>3</sup> permanent, 187 m <sup>3</sup> extended detention and a total volume of 2396 m <sup>3</sup> at a depth of 900mm, to store, attenuate and discharge stormwater into existing 525mm diameter Municipal Storm Sewer on Hamilton Road via an outlet control structure.
Design Storm	Quantity: 100-year storm
Reference ECA(s)	ECA number 0423-7TPPF6



Reference Works as part of treatment train	N/A
Brief Description:	A constructed wetland with a 600mm diameter pipe inlet into a forebay. A 1200mm diameter perforated CSP riser /outlet control structure manhole located in the pond bottom embankment surrounded with riprap complete with one (1) 80mm and one (1) 200mm diameter outlet orifices to discharge storm water into a 375mm diameter outlet pipe. A 2m wide by 300mm deep overflow spillway located on the pond embankment to discharge pond water into the existing Hamilton Roads right-of-way/side ditches via a channel beside the proposed townhouses.
Receive Emergency Sanitary Overflows	No
Notes / Additional Information	N/A

### Asset ID STWMF30 – Pab Holdings Stormwater Management Facility – Detention Pond

Location	Pab Holdings Phase 1, Forrest Meadows Subdivision southeast by Regional Road No.1.
Watershed/Subwatershed	Nith River watershed
Receiver of discharge	Runoff from approximately 1.6 ha drains off-site towards the northeast. Additional runoff will be conveyed to the existing Forrest Meadows stormwater management basin.
Outlet location	43.389287, -80.711046
Catchment Area	5.1 ha
Level of Treatment for suspended solids	Assumed Level 1, 60% TSS removal
Treatment for other contaminants, as required	N/A
Level of Volume control	A permanent storage volume of 2 m <sup>3</sup> , an extended detention storage volume of 115 m <sup>3</sup> and a total active storage volume of 1924 m <sup>3</sup> .
Design Storm	Quantity: 5-year storm and 100-year storm  In-line storm water management detention basin to maintain the peak 5 and 100-year flow rates at or below the pre-development rates, and to maintain the 100-year runoff

	volume in excess of the storm sewer capacity at or below the existing volume.
Reference ECA(s)	Missing ECA
Reference Works as part of treatment train	N/A
Brief Description:	Missing information
Receive Emergency Sanitary Overflows	No
Notes / Additional Information	N/A

### Asset ID STWMF3 & STWMF5 – Poth Stormwater Management Facility – Detention Ponds

Location	Poth Residential Subdivision, Lot 22 and Lot 39, Village of New Dundee, Township of Wilmot
Watershed/Subwatershed	Alder Creek watershed
Receiver of discharge	Pond #1 (STWMF5) discharging to Queen Street (Regional Road 13) ditch Pond #2 (STWMF3) discharging to Bridge Street (Township Road No. 9) ditch
Outlet location	Pond #1 43.344865, -80.534580, Pond #2 43.348754, -80.538754
Catchment Area	6.32 ha
Level of Treatment for suspended solids	Assumed Level 1, 60% TSS removal
Treatment for other contaminants, as required	N/A
Level of Volume control	Pond #1 – 654 m <sup>3</sup> storage capacity for 100-year storm Pond #2 – 1089 m <sup>3</sup> storage capacity for 100-year storm
Design Storm	Quantity: 5-year storm and 100-year storm

Reference ECA(s)	ECA number 3-1749-88-006
Reference Works as part of treatment train	N/A
Brief Description:	Pond 1 & 2 have an outlet manhole with an outlet pipe with a 230mm orifice plate and weir.
Receive Emergency Sanitary Overflows	No
Notes / Additional Information	N/A

#### Asset ID STWMF23 – Reinhart Stormwater Management Facility – Wet Pond

Location	Petersburg Subdivision, South of Snyders Road, Part Lot 6, Wilmot Township
Watershed/Subwatershed	Alder Creek
Receiver of discharge	Discharging to the culvert under Regional Road No. 12, and via an easement to the tributary of Alder Creek, including temporary sediment and erosion control measures.
Outlet location	43.410947, -80.601156
Catchment Area	5.85 ha
Level of Treatment for suspended solids	Assumed Level 1, 60% TSS removal
Treatment for other contaminants, as required	N/A
Level of Volume control	The pond having a permanent storage volume of 839 m <sup>3</sup> , an active storage volume of 1836 m <sup>3</sup> , a total available pond volume of 2,674 m <sup>3</sup>
Design Storm	Quantity: 100-year storm
Reference ECA(s)	ECA number 6681-5GPS75

Reference Works as part of treatment train	N/A
Brief Description:	With lot level controls, conveyed to the stormwater management pond by a system of storm sewers, surface ditches and overland flow, with the inlet to the pond from a 885x1345 millimetre elliptical storm pipe. Quality control, complete with one inlet structure, one (1) sediment forebay, a wet pond, micro-pool, emergency spillway and an outlet structure complete with a 0.75 metre diameter orifice
Receive Emergency Sanitary Overflows	No
Notes / Additional Information	N/A

#### Asset ID STWMM11 – Riverwoods Stormwater Management Facility – Wet Pond

Location	Riverwood Estates Subdivision, New Hamburg
Watershed/Subwatershed	Nith River
Receiver of discharge	Conveyed by an 825mm diameter pipe to the Nith River. Overland flow is therefore approximately 0.88 cms (2.13 1.25). It is proposed that a grassed swale will direct this flow to the river parallel to the outlet pipe.
Outlet location	43.383563, -80.723250
Catchment Area	19.96ha – Drainage area plan not attached in Appendix 4.
Level of Treatment for suspended solids	Assumed Level 1, 60% TSS removal
Treatment for other contaminants, as required	N/A
Level of Volume control	Unknown
Design Storm	Quantity: 5-year storm and 100-year storm
Reference ECA(s)	Missing ECA
Reference Works as part of treatment train	N/A
Brief Description:	The drainage swale is proposed to be a trapezoid channel with 4:1 slopes and a 2.0 m bottom. At the outlet of the pipe and swale a concrete headwall is proposed and

	downstream of this point a ditch will convey the flows to the Nith river.
Receive Emergency Sanitary Overflows	No
Notes / Additional Information	N/A

#### Asset ID STWMF14 – Shephard Stormwater Management Facility – Detention Pond

Location	Riverwood Estates Subdivision located on Part of Lot 22, Township of Wilmot
Watershed/Subwatershed	Nith River
Receiver of discharge	Outfall to discharge to the Nith River.
Outlet location	43.371605, -80.697983
Catchment Area	9.42 ha
Level of Treatment for suspended solids	Assumed Level 1, 60% TSS removal
Treatment for other contaminants, as required	N/A
Level of Volume control	Constructed detention pond with approximate volumes of 7.3 m <sup>3</sup> in permanent and 833 m <sup>3</sup> in active storage capacity (100yr)
Design Storm	Quantity: 5-year storm and 100-year storm
Reference ECA(s)	ECA number 3-0442-93-006
Reference Works as part of treatment train	N/A
Brief Description:	Sized for the retention of runoff from a 25mm storm of 2 hour duration and a controlled outlet with slow release over 24 hours, including overflow spillway, control structures and outfall.
Receive Emergency Sanitary Overflows	No

Notes / Additional Information	N/A
--------------------------------	-----

**Asset ID STWMF1 – Strauss Stormwater Management Facility – Dry Pond**

Location	Strauss Court Subdivision, part of Lot 6, Township of Wilmot
Watershed/Subwatershed	Alder Creek Watershed
Receiver of discharge	Private property roll #301808000806300
Outlet location	43.435943, -80.621726
Catchment Area	7.97 ha
Level of Treatment for suspended solids	Assumed Level 1, 60% TSS removal
Treatment for other contaminants, as required	N/A
Level of Volume control	Modelled 100yr Active Storage Capacity of ~500 m <sup>3</sup>
Design Storm	Quantity: 100-year storm
Reference ECA(s)	ECA number 3-1290-80-16
Reference Works as part of treatment train	N/A
Brief Description:	600mm diameter outlet pipe under Regional Rd. 9
Receive Emergency Sanitary Overflows	No
Notes / Additional Information	N/A

**Asset ID STWMF12 – Sugarlane Ridge Stormwater Management Facility – Wet Pond**

Location	Sugarlane Ridge Subdivision Phase 2, Part of Lot 21, Concession South of Snyder's Road
Watershed/Subwatershed	Nith River
Receiver of discharge	Discharging to Ivan Gingerich Municipal Drain
Outlet location	43.393919, -80.708626
Catchment Area	11.09 ha
Level of Treatment for suspended solids	Assumed Level 1, 60% TSS removal
Treatment for other contaminants, as required	N/A
Level of Volume control	A permanent pool of 1482 m <sup>3</sup> , an extended retention volume of 444 m <sup>3</sup> and a total storage volume of 6188 m <sup>3</sup>
Design Storm	Quantity: 25mm event, 5-year storm and 100-year storm
Reference ECA(s)	ECA number 5063-868RLH
Reference Works as part of treatment train	N/A
Brief Description:	Conveyed via storm sewers and overland drainage swales to the quality and quantity control pond complete with inlet structure, forebay, overflow weir and outlet structure together with an orifice chamber housing a 200mm dia orifice on the pipe cap of the riser pipe and a 150mm dia orifice on the pipe cap of the 300mm outlet pipe allowing a maximum discharge of 0.31 m <sup>3</sup> /s(5y storm event) and of 0.111 m <sup>3</sup> /s(100y storm event) to the existing 450mm dia storm sewer at MH9 on the north side of the pond, ultimately discharging into Ivan Gingerich Minicipal Drain
Receive Emergency Sanitary Overflows	No

Notes / Additional Information	N/A
--------------------------------	-----

**Asset ID STWMF31 – Sunvest Stormwater Management Facility – Hybrid Wet Pond/Wetland**

Location	Catherine Street Subdivision, Part of Blocks L and M, Smith's Plan, Town of New Hamburg, Township of Wilmot
Watershed/Subwatershed	Nith River
Receiver of discharge	discharging via a 200 mm diameter outlet pipe and a ditch inlet catchbasin, together allowing a maximum discharge of 0.091 mVs (5-year return storm) via a 450 mm diameter outlet pipe, a concrete headwall, rip-rap, a stone-lined drainage ditch and the existing drainage channel to the Nith River
Outlet location	43.382231, -80.723490
Catchment Area	91.9 ha
Level of Treatment for suspended solids	Normal Level water quality protection and erosion control
Treatment for other contaminants, as required	N/A
Level of Volume control	A permanent storage volume of 5,822 m <sup>3</sup> , an extended detention storage volume of 6,822 m <sup>3</sup> and a total active storage volume of 36,634 m <sup>3</sup>
Design Storm	Quantity: 5-year storm and 100-year storm
Reference ECA(s)	ECA number 5063-868RLH
Reference Works as part of treatment train	N/A
Brief Description:	Complete with one (1) inlet structure consisting of a 1,500 mm diameter inlet pipe, a concrete headwall with energy dissipation blocks and rip-rap, a 60 m long sediment forebay, a forebay berm, a permanent pool, two (2)-4 m wide turfstone access ramps, a 4 m wide turfstone access path, a 40 m wide turfstone overflow weir and one (1) outlet structure consisting of a micropool, a 1.5 m diameter perforated CSP riser surrounded by rip-rap, housing a 200 mm diameter Hickenbottom standpipe



Receive Emergency Sanitary Overflows	No
Notes / Additional Information	N/A

### Asset ID STWMF21 & STWMF25 – Victoria St Stormwater Management Facility – Wet Ponds

Location	New Hamburg Road Corridor Reconstruction, Part Lot 4, Plan 885, Marvin St./Hamilton Rd., Wilmot Township
Watershed/Subwatershed	Nith River
Receiver of discharge	Pond 21 and 25 discharging to Nith River
Outlet location	Pond #1 (STWMF21) 43.382351, -80.706918 Pond #2 (STWMF25) 43.380312, -80.703718
Catchment Area	9.42ha
Level of Treatment for suspended solids	Assumed Level 1, 60% TSS removal for both ponds
Treatment for other contaminants, as required	N/A
Level of Volume control	Pond #1 a total storage volume of 1,032 m <sup>3</sup> ., consisting of a 543 m <sup>3</sup> permanent pool, 271 m <sup>3</sup> extended storage and a 218 m <sup>3</sup> flood attenuation storage volume  Pond #2 a total storage volume of 1,111 m <sup>3</sup> , consisting of a 598 m <sup>3</sup> permanent pool, 284 m <sup>3</sup> extended storage and a 229 m <sup>3</sup> flood attenuation storage volume
Design Storm	Quantity: 25mm storm to 100-year storm
Reference ECA(s)	ECA number 6931-5A7J8D
Reference Works as part of treatment train	N/A
Brief Description:	Pond 1 equipped with outlet control structure c/w outlet channel (grassed) with erosion control check dams Pond 2 equipped with outlet control structure, and the outlets with erosion check dams
Receive Emergency Sanitary Overflows	No
Notes / Additional Information	Pond are on private property

**Asset ID STWMF7 & STWMF32 – Village Green Stormwater Management Facility –  
Detention Ponds**

Location	Meadowcreek Subdivision, Community of Baden, Township of Wilmot
Watershed/Subwatershed	Baden Creek tributary
Receiver of discharge	Pond #1 (STWMF32) discharges to Heipel pond Pond #2 (STWMF7) discharges to drainage ditch along Regional Road 6
Outlet location	STWMF7 43.399166, -80.659148 STWMF32 43.401175, -80.659683
Catchment Area	Pond 1 – 3.2ha Pond 2 – 1.67ha
Level of Treatment for suspended solids	Assumed Level 1, 60% TSS removal
Treatment for other contaminants, as required	N/A
Level of Volume control	Pond #1 active storage volume of 10,595 m <sup>3</sup> Pond #2 active storage volume of 393 m <sup>3</sup>
Design Storm	Quantity: 5-year and 100-year storm
Reference ECA(s)	ECA number 3-0624-89-006
Reference Works as part of treatment train	N/A
Brief Description:	Pond 1 equipped with 450mm diameter outlet for minor flows, 1100mm diameter for major flows Pond 2 equipped with 450mm diameter outlet for minor flows with 120mm diameter orifice plate Including overflow weirs for both ponds.
Receive Emergency Sanitary Overflows	No
Notes / Additional Information	N/A

**Asset ID STWMF4 – Woodridge Green Stormwater Management Facility – Detention Pond**

Location	Simon-Wood Subdivision, south of Bleam's Road, Settlement Area of Mannheim, Township of Wilmot
Watershed/Subwatershed	Alder Creek
Receiver of discharge	Grassed ditch conveys runoff water across the Simon Wood property into Alder Creek.
Outlet location	43.396124, -80.544056
Catchment Area	10.2 ha
Level of Treatment for suspended solids	Assumed Level 1, 60% TSS removal
Treatment for other contaminants, as required	N/A
Level of Volume control	Active storage capacity of 2500 m <sup>3</sup>
Design Storm	Quantity: 5-year storm and 100-year storm
Reference ECA(s)	ECA number 3-1721-86-006
Reference Works as part of treatment train	N/A
Brief Description:	The drainage is from east to west via the draw that channels the runoff water into an existing 900 mm (36") corrugated steel culvert crossing under Mannheim Road with a 3.0% slope. Drainage through the culvert outlets flows into an existing grassed ditch.
Receive Emergency Sanitary Overflows	No
Notes / Additional Information	N/A

**Stormwater Pumping Stations**

- 1.5 The following are identified Stormwater pumping stations in the Authorized System:

**N/A**

Asset ID and Name	N/A
Site Location	
Watershed/Subwatershed	
Latitude and Longitude	
Coordinates (optional)	
Description	
Pumping Station Capacity	
Equipment	
Emergency Storage	
Equipment: Associated controls and Appurtenances	
Overflow	
Standby Power	
Notes	

**Third Pipe Collection System**

1.6 The following are identified third pipe systems in the Authorized System.

**N/A**

Asset ID and Name	N/A
Location	
Watershed/Subwatershed	
Receiver of discharge	
Outlet location	
Catchment Area	
Treatment, if applicable	
Reference ECA(s), if applicable	
Brief Description	
Notes	

**Other Works:**

1.7 The following works are part of Authorized System:

<b>Table B6: Other Works</b>			
Column 1 Asset ID / Name	Column 2 Site Location (Latitude & Longitude)	Column 3 Component	Column 4 Description
N/A	N/A	N/A	N/A

**Developer-Operated Facilities:**

- 1.8 The following facilities are part of the Authorized System, have been constructed, and are being operated by the developer under the authority of an agreement entered into with the Owner of the system.

<b>Table B7: Developer-Operated Facilities</b>			
Asset ID	Type of Facility	Location	Developer Name
N/A	N/A	N/A	N/A

- 1.9 The Owner shall notify the Director, using the Director Notification Form, within thirty (30) days where the operation of any Facility identified in Table B7 has been:
- 1.9.1 Incorporated into the overall Stormwater Management System and assumed by an Operating Authority identified in Schedule B of this Approval.
- 1.9.2 Has been transferred from the developer identified in Table B7 to another party.

**Transitional – Facilities with Individual ECAs**

- 1.10 The following Facilities are connected to the Authorized System, but ownership has not been assumed by the Owner. These Sewage Works are not part of the Authorized System and will continue to have separate ECAs until the Facilities are assumed by the Owner.

<b>Table B8: Facilities with Individual ECAs</b>				
Asset ID	Type of Facility	Location	ECA Number	Developer Name
N/A	N/A	N/A	N/A	N/A

- 1.11 The Owner shall notify the Director, using the Director Notification Form, within thirty (30) days where the ownership of any Facility identified in Table B8 has been assumed by the Owner.
- 1.12 The Director Notification required in condition 1.11 shall include:
- 1.12.1 A request from the developer to revoke the ECA identified in Table B8; or
- 1.12.2 A copy of an agreement or other documentation that demonstrates that the municipality has assumed ownership of the Facility and that the ECA identified in Table B8 should be revoked.

**Schedule C: List of Notices of Amendment to this ECA:  
Additional Approved Sewage Works**

System Owner	<b>Wilmot, The Corporation of the Township of</b>
ECA Number	<b>078-S701</b>
System Name	<b>Township of Wilmot Stormwater Management System</b>
ECA Issue Date	<b>February 8th, 2023</b>

**1.0 General**

1.1 Table C1 provides a list of all notices of amendment to this Approval that have been issued pursuant to clause 20.3(1) of the EPA that impose terms and conditions in respect of the Authorized System after consideration of an application by the Director (Schedule C Notices).

<b>Table C1: Schedule C Notices</b>				
Column 1 Issue #	Column 2 Issue Date	Column 3 Description	Column 4 Status	Column 5 DN#
N/A	N/A	N/A	N/A	N/A

## Schedule D: General

System Owner	<b>Wilmot, The Corporation of the Township of</b>
ECA Number	<b>078-S701</b>
System Name	<b>Township of Wilmot Stormwater Management System</b>
ECA Issue Date	<b>February 8th, 2023</b>

### 1.0 Definitions

1.1 For the purpose of this Approval, the following definitions apply:

**“Adverse Effect(s)”** has the same meaning as defined in section 1 of the EPA.

**“Alteration(s)”** includes the following, in respect of the Authorized System, but does not include repairs to the system:

- a) An extension of the system,
- b) A replacement or retirement of part of the system, or
- c) A modification of, addition to, or enlargement of the system.

**“Appendix A”** means Appendix A of this Approval.

**“Approval”** means this Environmental Compliance Approval including any Schedules attached to it.

**“Appurtenance(s)”** has the same meaning as defined in O. Reg. 525/98 (Approval Exemptions) made under the OWRA.

**“Authorized System”** means the Sewage Works comprising the Municipal Stormwater Management System authorized under this Approval”.

**“Class Environmental Assessment Project”** means an Undertaking that does not require any further approval under the EAA if the proponent complies with the process set out in the Municipal Engineers Association Class Environmental Assessment document, (Municipal Class Environmental Assessment approved by the Lieutenant Governor in Council on October 4, 2000 under Order in Council 1923/2000), as amended from time to time.

**“Combined Sewer(s)”** means pipes that collect and transmit both sanitary Sewage and other Sewage from residential, commercial, institutional, and

industrial buildings and facilities and Stormwater through a single-pipe system, but does not include Nominally Separate Sewers.

**“Completion”** means substantial performance as described in s.2 (1) of the *Construction Act*, R.S.O. 1990, c. C.30.

**“Compound of Concern”** means a Contaminant that is discharged from the Facility in an amount that is not negligible.

**“Contaminant”** has the same meaning as defined in section 1 of the EPA.

**“CSO”** means a combined sewer overflow which is a discharge to the environment at designated location(s) from a Combined Sewer or Partially Separated Sewer that usually occurs as a result of precipitation when the capacity of the Sewer is exceeded. An intervening time of twelve hours or greater separating a CSO from the last prior CSO at the same location is considered to separate one overflow Event from another.

**“CWA”** means the *Clean Water Act*, R.S.O. 2006, c.22.

**“Design Criteria”** means the design criteria set out in the Ministry’s publication “Design Criteria for Sanitary Sewers, Storm Sewers and Forcemains for Alterations Authorized under Environmental Compliance Approval”, (as amended from time to time).

**“Design Guidelines for Sewage Works”** means the Ministry document titled “Design Guidelines for Sewage Works”, 2008 (as amended from time to time).

**“Director”** means a person appointed by the Minister pursuant to section 5 of the EPA for the purposes of Part II.1 of EPA (Environmental Compliance Approvals).

**“Director Notification Form”** means the most recent version of the Ministry form titled Director Notification – Alterations to a Municipal Stormwater Management System, as obtained directly from the Ministry or from the Ministry’s website.

**“District Manager”** means the district manager or a designated representative of the Local Ministry Office.

**“EAA”** means the *Environmental Assessment Act*, R.S.O. 1990, c. E.18.

**“EPA”** means the *Environmental Protection Act*, R.S.O. 1990, c.E.19.

**“ESC”** means erosion and sediment control.



**“Facility”** means the entire operation located on the property where the Sewage Works or equipment is located.

**“Form SW1”** means the most recent version of the Ministry form titled Record of Future Alteration Authorized for Storm Sewers/Ditches/Culverts as obtained directly from the Ministry or from the Ministry’s website.

**“Form SW2”** means the most recent version of the Ministry form titled Record of Future Alteration Authorized for Stormwater Management Facilities as obtained directly from the Ministry or from the Ministry’s website.

**“Form SW3”** means the most recent version of the Ministry form titled Record of Future Alteration Authorized for Third Pipe Collection Systems as obtained directly from the Ministry or from the Ministry’s website.

**“Licensed Engineering Practitioner”** means a person who holds a licence, limited licence, or temporary licence under the *Ontario Professional Engineers Act* R.S.O. 1990, c. P.28.

**“LID”** means “low impact development” a Stormwater management strategy that seeks to mitigate the impacts of increased runoff and Stormwater pollution by managing runoff as close to its source as possible. LID comprises a set of site design strategies that minimize runoff and distributed, small scale structural practices that mimic natural or predevelopment hydrology through the processes of infiltration, evapotranspiration, harvesting, filtration, and detention of Stormwater.

**“Local Ministry Office”** means the local office of the Ministry responsible for the geographic area where the Authorized System is located.

**“Minister”** means the Minister of the Ministry or such other member of the Executive Council as may be assigned the administration of the EPA and OWRA under the *Executive Council Act*, R.S.O. 1990, c. E.25.

**“Ministry”** means the Ministry of the Minister and includes all employees or other persons acting on its behalf.

**“Monitoring Plan”** means the monitoring plan prepared and maintained by the Owner under condition 4.1 in Schedule E of this Approval.

**“MTD”** means manufactured treatment device.

**“Municipal Drain”** has the same meaning as drainage works as defined in section 1 of the *Drainage Act* R.S.O. 1990, c. D.17.

**“Municipal Drainage Engineer’s Report”** means a report signed by a drainage engineer employed or contracted by a municipality and approved in writing by municipal council or equivalent.

**“Municipal Sewage Collection System”** means all Sewage Works, located in the geographical area of a municipality, that collect and transmit sanitary Sewage and are owned, or may be owned pursuant to an agreement with a municipality entered into under the *Planning Act* or *Development Charges Act*, 1997, by:

- a) A municipality, a municipal service board established under the *Municipal Act*, 2001 or a city board established under the *City of Toronto Act*, 2006; or
- b) A corporation established under sections 9, 10, and 11 of the *Municipal Act*, 2001 in accordance with section 203 of that Act or under sections 7 and 8 of the *City of Toronto Act*, 2006 in accordance with sections 148 and 154 of that Act.

**“Municipal Stormwater Management System”** means all Sewage Works, located in the geographical area of a municipality, that collect, transmit, or treat Stormwater and are owned, or may be owned pursuant to an agreement entered into under the *Planning Act* or *Development Charges Act*, 1997, by:

- a) A municipality, a municipal service board established under the *Municipal Act*, 2001 or a city board established under the *City of Toronto Act*, 2006; or
- b) A corporation established under sections 9, 10, and 11 of the *Municipal Act*, 2001 in accordance with section 203 of that Act or under sections 7 and 8 of the *City of Toronto Act*, 2006 in accordance with sections 148 and 154 of that Act.

**“Natural Environment”** has the same meaning as defined in section 1 of the EPA.

**“Nominally Separate Sewer(s)”** mean Separate Sewers that also have connections from roof leaders and foundation drains, and are not considered to be Combined Sewers.

**“OGS”** means Oil and Grit Separator(s).

**“Operating Authority”** means, in respect of the Authorized System, the person, entity, or assignee that is given responsibility by the Owner for the operation, management, maintenance, or Alteration of the Authorized System, or a portion of the Authorized System.

**"Owner"** for the purposes of this Approval means the Corporation of the township of the Wilmot, and includes its successors and assigns.

**"OWRA"** means the *Ontario Water Resources Act*, R.S.O. 1990, c. O.40.

**"O&M Manual"** means the operation and maintenance manual prepared and maintained by the Owner under condition 3.2 in Schedule E of this Approval.

**"Partially Separated Sewer(s)"** means Combined Sewers that have been retrofitted to transmit sanitary Sewage but in which roof leaders or foundation drains still contribute Stormwater inflow to the Partially Separated Sewer.

**"Pre-development"** means the more stringent of a site's:

- a) Existing condition prior to proposed development or construction activities; or
- b) Condition as defined by the local municipality.

**"Prescribed Person"** means a person prescribed in O. Reg. 208/19 (Environmental Compliance Approval in Respect of Sewage Works) for the purpose of ss. 20.6 (1) of the EPA, and where the alteration, extension, enlargement, or replacement is carried out under an agreement with the Owner.

**"Privately Owned Stormwater Works"** means Stormwater Sewage Works on private land that are privately owned and, while not part of the Authorized System, are considered part of a Stormwater Treatment Train.

**"Qualified Person (QP)"** means persons who have obtained the relevant education and training and have demonstrated experience and expertise in the areas relating to the work required to be carried out by this Approval.

**"Schedule C Notice(s)"** means notice(s) of amendment to this Approval issued pursuant to clause 20.3(1) of the EPA that imposes terms and conditions in respect of the Authorized System after consideration of an application by the Director.

**"Separate Sewer(s)"** means pipes that collect and transmit sanitary Sewage and other Sewage from residential, commercial, institutional, and industrial buildings.

**"Sewage"** has the same meaning as defined in section 1 of the OWRA.

**"Sewage Works"** has the same meaning as defined in section 1 of the OWRA.

“**Sewer**” has the same meaning as defined in section 1 of O. Reg. 525/98 under the OWRA.

“**Significant Drinking Water Threat**” has the same meaning as defined in section 2 of the CWA.

“**Significant Snowmelt Event(s)**” means the melting of snow at a rate which adversely affects the performance and function of the Authorized System and/or the Sewage Treatment Plant(s) identified in Schedule A of this Approval.

“**Significant Storm Event(s)**” means a minimum of 25 mm of rain in any 24 hours period.

“**Source Protection Authority**” has the same meaning as defined in section 2 of the CWA.

“**Source Protection Plan**” means a drinking water source protection plan prepared under the CWA.

“**SSO**” means a sanitary sewer overflow which is a discharge of Sewage from a Separate Sewer or Nominally Separate Sewer to the environment from designated location(s) in the Authorized System.

“**Standard Operating Policy for Sewage Works**” means the standard operating policy developed by the Ministry to assist in the implementation of Source Protection Plan policies related to Sewage Works and providing minimum design and operational standards and considerations to mitigate risks to sources of drinking water, as amended from time to time.

“**Storm Sewer**” means Sewers that collect and transmit, but not exfiltrate or lose by design, Stormwater resulting from precipitation and snowmelt.

“**Stormwater**” means rainwater runoff, water runoff from roofs, snowmelt, and surface runoff.

“**Stormwater Management Facility(ies)**” means a Facility for the treatment, retention, infiltration, or control of Stormwater.

“**Stormwater Management Planning and Design Manual**” means the Ministry document titled “Stormwater Management Planning and Design Manual”, 2003 (as amended from time to time).

“**Stormwater Treatment Train**” means a series of Stormwater Management Facilities designed to meet Stormwater management objectives (e.g., Appendix A) for a given area, and can consist of a combination of MTDs, LIDs and end-of-pipe controls.

“**TRCA**” means the Toronto Region Conservation Authority.

“**Third Pipe Collection System**” means Sewage Works designed to collect and transmit foundation drainage and/or groundwater to a receiving surface water or dry well;

“**Undertaking**” has the same meaning as in the EAA.

“**Vulnerable Area(s)**” has the same meaning as in the CWA.

## 2.0 General Conditions

- 2.1 The works comprising the Authorized System shall be constructed, installed, used, operated, maintained, replaced, or retired in accordance with the conditions of this Approval, which includes the following Schedules:

Schedule A – System Information

Schedule B – Municipal Stormwater Management System Description

Schedule C – List of Notices of Amendment to this ECA

Schedule D – General

Schedule E – Operating Conditions

Schedule F – Residue Management

Appendix A – Stormwater Management Criteria

- 2.2 The issuance of this Approval does not negate the requirements of other regulatory bodies, which includes but is not limited to, the Ministry of Northern Development, Mines, Natural Resources and Forestry and the local Conservation Authority.
- 2.3 Where there is a conflict between a provision of any document referred to in this Approval and the conditions of this Approval, the conditions in this Approval shall take precedence. Where there is a conflict between the information in a Schedule C Notice and another section of this Approval, the document bearing the most recent date shall prevail.
- 2.4 The Owner shall ensure that any person authorized to carry out work on or operate any aspect of the Authorized System is provided with a print or electronic copy of this Approval and the conditions herein and shall take all reasonable measures to ensure any such person complies with the same.
- 2.5 The conditions of this Approval are severable. If any condition of this Approval, or the application of any requirement of this Approval to any circumstance, is held invalid or unenforceable, the application of such condition to other circumstances and the remainder of this Approval shall not be affected thereby.

**3.0 Alterations to the Municipal Stormwater Management System**

- 3.1 For greater certainty, the Alterations authorized under this Approval are limited to Sewage Works comprising the Authorized System which does not include municipally or Privately Owned Stormwater Works:
- 3.1.1 On industrial, commercial, or institutional land;
  - 3.1.2 Serving a single parcel of land, unless the stormwater management facility is located on a municipally owned park or community center;
  - 3.1.3 That are operated as waste disposal sites defined under the EPA or snow dump / melt facilities; or,
  - 3.1.4 That propose to collect, store, treat, or discharge stormwater containing substances or pollutants (other than Total Suspended Solids, or oil and grease) detrimental to the environment or human health.
- 3.2 Any Schedule C Notice shall provide authority to alter the Authorized System in accordance with the conditions of this Approval.
- 3.3 All Schedule C Notices issued by the Director for the Municipal Stormwater Management System shall form part of this Approval.
- 3.4 The Owner and a Prescribed Person shall ensure that the documentation required through conditions in this Approval and the documentation required in the Design Criteria are prepared for any Alteration of the Authorized System.
- 3.5 The Owner shall notify the Director within thirty (30) calendar days of placing into service or Completion of any Alteration of the Authorized System which had been authorized:
- 3.5.1 Under Schedule D to this Approval where the Alteration results in a change to Sewage Works specifically described in Schedule B of this Approval;
  - 3.5.2 Through a Schedule C Notice respecting Sewage Works other than Storm Sewers; or
  - 3.5.3 Through another approval that was issued under the EPA prior to the issue date of this Approval.
- 3.6 The notification requirements set out in condition 3.5 do not apply to any Alteration in respect of the Authorized System which:
- 3.6.1 Is exempt under section 53(6) of the OWRA or by O. Reg. 525/98;

- 3.6.2 Constitutes maintenance or repair of the Authorized System; or
- 3.6.3 Is a Storm Sewer, ditch, or culvert authorized by condition 4.1 of Schedule D of this Approval.
- 3.7 The Owner shall notify the Director within ninety (90) calendar days of:
  - 3.7.1 The discovery of existing Sewage Works not described or depicted in Schedule B, or
  - 3.7.2 Additional or revised information becoming available for any Sewage Works described in Schedule B of this Approval.
- 3.8 The notifications required in condition 3.5 and 3.7 shall be submitted to the Director using the Director Notification Form.
- 3.9 The Owner shall ensure that any chemicals, coagulants, or polymers used in the Authorized System have obtained written approval from the Director prior to use, unless required for spill control or spill clean-up.
- 3.10 The Owner shall ensure that an ESC plan is prepared, and temporary ESC measures are installed in advance of and maintained during any construction activity on the Authorized System, subject to the following conditions:
  - 3.10.1 Inspections of ESC measures are to be conducted at a frequency specified per the ESC plan, for dry weather periods (active and inactive construction phases), after Significant Storm Events and Significant Snowmelt Events, and after any extreme weather events.
  - 3.10.2 Any deficiencies shall be addressed, and any required maintenance actions(s) shall be undertaken as soon as practicable once they have been identified.
  - 3.10.3 Inspections and maintenance of the temporary ESC measures shall continue until they are no longer required.
- 3.11 The Owner shall ensure that records of inspections required by this Approval during any construction activity, including those required under condition 3.10:
  - 3.11.1 Include the name of the inspector, date of inspection, visual observations, and the remedial measures, if any, undertaken to maintain the temporary ESC measures.

- 3.11.2 Be retained with records relating to the Alteration that the construction relates to, such as the form required in conditions 4.4.1, 5.5.1, and 6.2.1 of Schedule D, or the Schedule C Notice.
- 3.11.3 Be retrievable and made available to the Ministry upon request.
- 3.12 The document(s) or file(s) referenced in Table B1 of Schedule B of this Approval shall:
  - 3.12.1 Be retained by the Owner;
  - 3.12.2 Include at a minimum:
    - a) Identification of Storm Sewers, which shall include the following information:
      - i Location relative to street names or easements; and
      - ii Sewer diameters.
    - b) Identification of existing municipally owned Stormwater Sewage Works, including but not limited to ditches, swales, culverts, outlets, Stormwater Management Facilities, sedimentation MTD (for example oil grit separators), filtration MTD, LID, end of pipe controls, Third Pipe Collection Systems, and pumping stations, including any applicable Asset IDs.
    - c) Identification of the main tributaries and receiving water bodies that the Sewage Works discharge to.
    - d) Delineation of municipal, watershed, and subwatershed boundaries, as available.
    - e) Identification of the storm sewersheds for each outlet.
    - f) Identification of any source protection Vulnerable Areas.
    - g) Identification of any Sewage Works that receive SSOs or CSOs.
  - 3.12.3 Be updated to include:
    - a) Alterations authorized under Schedule D of this Approval or through a Schedule C Notice within twelve (12) months of the Alteration being placed into service.
    - b) Updates to information contained in the document(s) or files(s) not associated with an Alteration within twelve (12) months of becoming aware of the updated information.



- 3.13 An Alteration is not authorized under Schedule D of this Approval for projects that impact Indigenous treaty rights or asserted rights where:
- 3.13.1 The project is on Crown land or would alter access to Crown land;
  - 3.13.2 The project is in an open or forested area where hunting, trapping or plant gathering occur;
  - 3.13.3 The project involves the clearing of forested land unless the clearing has been authorized by relevant municipal, provincial, or federal authorities, where applicable;
  - 3.13.4 The project alters access to a water body;
  - 3.13.5 The proponent is aware of any concerns from Indigenous communities about the proposed project and these concerns have not been resolved; or,
  - 3.13.6 Conditions respecting Indigenous consultation in relation to the project were placed in another permit or approval and have not been met.
- 3.14 No less than 60 days prior to construction associated with an Alteration the Director may notify the Owner in writing that a project is not authorized through Schedule D of this Approval where:
- 3.14.1 Concerns regarding treaty rights or asserted rights have been raised by one or more Indigenous communities that may be impacted by the Alteration; or
  - 3.14.2 The Director believes that it is in the public interest due to site specific, system specific, or project specific considerations.
- 3.15 Where an Alteration is not authorized under condition 3.13 or 3.14 above:
- 3.15.1 An application respecting the Alteration shall be submitted to the Ministry; and,
  - 3.15.2 The Alteration shall not proceed unless:
    - a) Approval for the Alteration is granted by the Ministry (i.e., a Schedule C Notice); or,
    - b) The Director provides written notice that the Alteration may proceed in accordance with conditions in Schedule D of this Approval.

**4.0 Authorizations of Future Alterations to Storm Sewers, Ditches, or Culverts - Additions, Modifications, Replacements and Extensions**

4.1 The Owner or a Prescribed Person may alter the Authorized System by adding, modifying, replacing, or extending a Storm Sewer, ditch, or culvert within the Authorized System subject to the following conditions and conditions 4.2 and 4.3 below:

4.1.1 The design of the addition, modification, replacement, or extension:

- a) Has been prepared by a Licensed Engineering Practitioner;
- b) Has been designed only to collect and transmit Stormwater;
- c) Has not been designed to collect or treat any sanitary Sewage;
- d) Has not been designed to collect, store, treat, control, or manage groundwater, unless for the purpose of foundation drains, road subdrains, or LIDs;
- e) Satisfies the Design Criteria or any municipal criteria that have been established that exceed the minimum requirements set out in the Design Criteria;
- f) Satisfies the standards set out in Ontario Provincial Standard Specifications (OPSS) and Ontario Provincial Standard Drawings (OPSD), as applicable to ditches and culverts;
- g) Is consistent with or otherwise addresses the design objectives contained within the Design Guidelines for Sewage Works;
- h) Is planned, designed, and built to be consistent with the Stormwater Management Planning and Design Guidance Manual. If there is a conflict with Appendix A of this Approval, then Appendix A shall prevail; and
- i) Includes design considerations to protect sources of drinking water, including those set out in the Standard Operating Policy for Sewage Works, and any applicable local Source Protection Plan policies.

4.1.2 The addition, modification, replacement, or extension shall be designed so that it will:

- a) Not adversely affect the ability to maintain a gravity flow in the Authorized System without overflowing or increase surcharging in any maintenance holes as per design; and
  - b) Provide smooth flow transition to existing gravity Storm Sewers.
- 4.1.3 The Alteration shall not result in:
- a) Adverse Effects; or
  - b) A deterioration of the approved effluent quality or quantity of downstream Stormwater Management Facilities which results in not being able to achieve the overall Stormwater performance criteria per Appendix A.
- 4.1.4 The Storm Sewer, ditch or culvert addition, modification, replacement, or extension is wholly located within the municipal boundary over which the Owner has jurisdiction or there is a written agreement in place with the adjacent property owner respecting the Alteration and resulting Sewage Works.
- 4.1.5 The Owner consents in writing to the addition, modification, replacement, or extension.
- 4.1.6 A Licensed Engineering Practitioner has verified in writing that the addition, modification, replacement, or extension meets the requirements of conditions 4.1.1 a) to h), 4.3.9, and 4.3.10.
- 4.1.7 The Owner has verified in writing that the addition, modification, replacement, or extension has complied with inspection and testing requirements in the Design Criteria.
- 4.1.8 The Owner has verified in writing that the addition, modification, replacement, or extension meets the requirements of conditions 4.1.1 i), 4.1.2 to 4.1.6, 4.3.7, and 7.2.
- 4.2 The addition of Storm Sewers or ditches can be constructed but not operated until the Stormwater Management Facilities required to service the new Storm Sewers or ditches are in operation.
- 4.3 The Owner or a Prescribed Person is not authorized to undertake an Alteration described above in condition 4.1 where the Alteration relates to the addition, modification, replacement, or extension of a Storm Sewer that:
- 4.3.1 Passes under or through a body of surface water, unless trenchless construction methods are used or the local Conservation Authority has authorized an alternative construction method.

- 4.3.2 Has a nominal diameter greater than 2,400 mm, or equivalent sizing.
- 4.3.3 Is a Combined Sewer.
- 4.3.4 Is a concrete channel.
- 4.3.5 Is designed to, at any time, transmit, store, or control sanitary Sewage.
- 4.3.6 Converts rural road cross section ditches to curb, gutter, and Storm Sewers if the Stormwater volume and/or peak flow is increased and no water quality treatment is planned or demonstrated to be achieved, in accordance with this Approval and Appendix A, to offset the increase in Stormwater.
- 4.3.7 Results in new discharges or increased discharges to a Municipal Drain without written approval by the Owner and a signed Municipal Drainage Engineer's Report in accordance with the *Drainage Act* R.S.O. 1990, c. D.17.
- 4.3.8 Establishes a new outlet with direct discharge into the Natural Environment without monitoring in accordance with this Approval and without achieving the requirements set in Appendix A.
- 4.3.9 Increases Stormwater flow of an existing Storm Sewer or ditch without achieving water quality criteria set in Appendix A in accordance with this Approval unless the existing downstream Municipal Stormwater Management System has sufficient residual transmission and treatment capacity to accommodate the additional Stormwater.
- 4.3.10 Increases local hydraulic capacity of an existing Storm Sewer or ditch to accommodate new Stormwater flows unless the existing downstream Municipal Stormwater Management System has sufficient residual hydraulic capacity to accommodate the additional Stormwater.
- 4.3.11 Connects to another Municipal Stormwater Management System, unless:
  - a) Prior to construction, the Owner of the Authorized System obtains written consent from the Owner or Owner's delegate of the Municipal Stormwater System being connected to; and
  - b) The Owner of the Authorized System retains a copy of the written consent from the Owner or Owner's delegate of the Municipal Stormwater Management System being connected

to as part of the record that is recorded and retained under condition 4.4.

4.3.12 Is part of an Undertaking in respect of which:

- a) A request under s.16(6) of the EAA has been made, namely a request that the Minister make an order under s.16;
- b) The Minister has made an order under s.16; or
- c) The Director under that EAA has given notice under s.16.1 (2) that the Minister is considering making an order under s.16.

4.4 The consents and verifications required in conditions 4.1 and 4.3, if applicable, shall be:

4.4.1 Recorded on Form SW1, prior to the Storm Sewer, ditch, or culvert addition, modification, replacement, or extension being placed into service; and

4.4.2 Retained for a period of at least ten (10) years by the Owner.

4.5 For greater certainty, the verification requirements set out in condition 4.4 do not apply to any Alteration in respect of the Authorized System which:

4.5.1 Is exempt under section 53(6) of the OWRA or by O. Reg. 525/98; or

4.5.2 Constitutes maintenance or repair of the Authorized System.

## **5.0 Authorizations of Future Alterations to Stormwater Management Facilities - Additions, Modifications, Replacement, and Extensions**

5.1 Subject to conditions 5.2 and 5.3, the Owner or a Prescribed Person may alter the Stormwater Management Facilities in the Authorized System by adding, modifying, replacing, or extending the following components:

5.1.1 Rooftop storage

5.1.2 Parking lot storage

5.1.3 Superpipe storage

5.1.4 Reduced lot grading

5.1.5 Roof leader to ponding area

5.1.6 Roof leader to soakaway pit

- 5.1.7 Infiltration trench
  - 5.1.8 Engineered grassed swales / bioswale
  - 5.1.9 Pervious pipes
  - 5.1.10 Pervious catchbasins
  - 5.1.11 Vegetated filter strips
  - 5.1.12 Natural buffer strips
  - 5.1.13 Green roofs/Rooftop gardens
  - 5.1.14 Wet pond
  - 5.1.15 Engineered wetland
  - 5.1.16 Dry pond
  - 5.1.17 Hybrid Facility
  - 5.1.18 Infiltration basin
  - 5.1.19 Filtration MTD
  - 5.1.20 Sedimentation MTD - OGS
  - 5.1.21 LID that relies on one or more of the following mechanisms to achieve treatment and control:
    - a) Evapotranspiration;
    - b) Infiltration into the ground; or
    - c) Filtration.
  - 5.1.22 Any other Stormwater Management Facilities where the Director has provided authorization in writing to proceed with the Alteration.
- 5.2 Any Alteration to the Authorized System authorized under condition 5.1 is subject to the following conditions:
- 5.2.1 The design of the Alteration shall:
    - a) Be prepared by a Licensed Engineering Practitioner;

- b) Be designed only to collect, receive, treat, or control only Stormwater and has not been designed to collect, receive, treat, or control sanitary Sewage;
- c) Be planned, designed, and built to be consistent with the Stormwater Management Planning and Design Guidance Manual. If there is a conflict with Appendix A of this Approval, then Appendix A shall prevail;
- d) Satisfy the Design Criteria or any municipal criteria that have been established that exceed the minimum requirements set out in the Design Criteria;
- e) Be part of a Stormwater Treatment Train approach that satisfies the requirements outlined in Appendix A, or transmits Stormwater to a Stormwater Management Facility that satisfies the requirements outlined in Appendix A;
- f) Include an outlet or an emergency overflow for the Sewage Works, with the verification of the location, route, and capacity of the receiving major system to accommodate overflows; and
- g) Include design considerations to protect sources of drinking water, including those set out in the Standard Operating Policy for Sewage Works and any applicable local Source Protection Plan policies.

5.2.2 The Alteration shall not result in:

- a) Adverse Effects; or
- b) A deterioration on the approved effluent quality or quantity of downstream Stormwater Management Facilities which results in not being able to achieve the overall Stormwater performance criteria per Appendix A.

5.2.3 The Alteration may incorporate co-benefits, but in doing so shall not diminish functionality or efficiency of any Stormwater Management Facility(ies) that may be impacted by the Alteration.

5.2.4 Any new sedimentation MTD that is part of the Alteration shall meet the following requirements:

- a) Tested in accordance with the TRCA protocol Procedure for Laboratory Testing of OGSs and testing data verified in accordance with the ISO 14034 Environmental Technology Verification (ETV) protocol. The suspended solids removal claimed for the sedimentation MTD in achieving the water

quality criteria in Appendix A, and the sizing methodology used to determine the appropriate sedimentation MTD dimensions for the particular site, shall be based on the verified removal efficiency for all particle size fractions comprising the particle size distribution specified within the testing protocol or a particle size distribution approved by the Director.

- b) Using the verified sediment removal efficiencies for the respective surface loading rates specified in the testing protocol, the sedimentation MTD sizing methodology shall use linear interpolation to calculate sediment removal efficiencies for surface loading rates that lie between the specified surface loading rates. For surface loading rates less than the lowest specified and tested surface loading rate, the sediment removal efficiency shall be assumed to be identical to the verified removal efficiency for the lowest specified and tested surface loading rate. Where available, 15 min rainfall stations shall be used for sizing the sedimentation MTD.
- c) When two or more sedimentation MTD are installed in series, no additional sediment removal credit shall be applied beyond the sediment removal credit of the largest device in the series.
- d) The sediment removal rate at the specified surface loading rates determined for the tested full scale, commercially available MTD may be applied to similar MTDs of smaller or larger size by proper scaling. Scaling the performance results of the tested MTD to other model sizes without completing additional testing is acceptable provided that:
  - i) The claimed sediment removal efficiencies for the similar MTD are the same or lower than the tested MTD at identical surface loading rates; and
  - ii) The similar MTD is scaled geometrically proportional to the tested unit in all inside dimensions of length and width and a minimum of 85% proportional in depth.
- e) The units must be installed in an off-line configuration if the unit had an effluent concentration greater than 25 mg/L at any of the surface loading rates conducted during the sediment scour and resuspension test as part of the ISO 14034 verification.
- f) The sedimentation MTD should be sized for the highest suspended solids percent removal physically and



economically practicable, and used as a pre-treatment device in a treatment train designed to achieve the water quality criteria in Appendix A.

5.2.5 Any new filtration MTD that is part of the Alteration shall meet the following requirements:

- a) Field tested and verified in accordance with a minimum of one of the following protocols:
  - i Washington State Technology Assessment Protocol - Ecology (TAPE) General Use Level Designation (GULD); and
    - 1. Has ISO 14034 ETV verification to satisfy ETV Canada requirements;
    - 2. The field monitoring data set used to obtain GULD certification should include a minimum of three (3) events that exceed 75th percentile rainfall event with at least one hour with an intensity of 6 mm/h or greater.
  - ii Another testing and verification method, where the Director has communicated acceptability in writing.
- b) Where available, 15 min rainfall stations shall be used for sizing the filtration MTD using the rainfall intensity corresponding to 90% of annual runoff volume;
- c) The SS removal rate determined for the tested full scale, commercially available filtration MTD, or single full-scale commercially available cartridge or filtration module, may be applied to other model sizes of that filtration MTD provided that appropriate scaling principles are applied. Scaling the tested filtration MTD or single full-scale commercially available cartridge or filtration module, to determine other model sizes and performance without completing additional testing is acceptable provided that:
  - i Depth of media, composition of media, and gradation of media remain constant.
  - ii The ratio of the maximum treatment flow rate to effective filtration treatment area (filter surface area) is the same or less than the tested filtration MTD;

- iii The ratio of effective sedimentation treatment area to effective filtration treatment area is the same or greater than the tested filtration MTD; and
  - iv The ratio of wet volume to effective filtration treatment area is the same or greater than the tested filtration MTD.
- 5.2.6 When it is necessary to use Privately Owned Stormwater Works in the Stormwater Treatment Train to achieve Appendix A criteria as part of or as a result of an Alteration, the following conditions apply:
  - a) The Owner shall, through legal instruments or binding agreements, obtain the right to access, operate, and maintain the Privately Owned Sewage Works;
  - b) The Owner shall ensure that the right to access, operate and maintain the Privately Owned Sewage Works described in condition 5.2.6 a) above is maintained at all times that the works are in service and used to achieve Appendix A criteria.
  - c) The Owner shall ensure on-going operation and maintenance of the Privately Owned Stormwater Works; and,
  - d) The Owner shall ensure that the Privately Owned Stormwater Works have obtained separate approval(s) under the EPA, as required.
- 5.2.7 The Alteration is wholly located within the municipal boundary over which the Owner has jurisdiction or there is a written agreement in place with the adjacent municipality respecting the Alteration and resulting Sewage Works.
- 5.2.8 The Owner consents in writing to the Alteration authorized under condition 5.1.
- 5.2.9 A Licensed Engineering Practitioner has verified in writing that the Alteration authorized under condition 5.1 meets the design requirements of conditions 5.2.1 a) to f), 5.2.4 and 5.2.5.
- 5.2.10 The Owner has verified in writing that the Alteration authorized under condition 5.1 meets the requirements of conditions 5.2.1 g), 5.2.2, 5.2.6 to 5.2.9, 5.3, 5.4, and 7.2.
- 5.3 The authorization in condition 5.1 does not apply:
  - 5.3.1 To the establishment of a regional end-of-pipe flood control Facility;

- 5.3.2 Where the Alteration will result in new or increased discharges to a Municipal Drain without written approval by the Owner and a signed Municipal Drainage Engineer's Report in accordance with the *Drainage Act* R.S.O. 1990, c. D.17;
- 5.3.3 To the establishment of a new outlet with direct discharge into the Natural Environment without treatment and monitoring in accordance with this Approval;
- 5.3.4 Where the Alteration will service a drainage area greater than 65 ha;
- 5.3.5 Where the Alteration will result in conversion of an existing Stormwater Management Facility into another type of Stormwater Management Facility;
- 5.4 Any Alteration to LID or end-of-pipe Stormwater Management Facilities shall be inspected before operation of the Alteration to confirm construction as per specifications (including depth, as applicable).
- 5.5 The consents and verifications required in conditions 5.2.8 to 5.2.10 if applicable, shall be:
  - 5.5.1 Recorded on Form SW2, prior to undertaking the Alteration;  
and
  - 5.5.2 Retained for a period of at least ten (10) years by the Owner.
- 5.6 For greater certainty, the verification requirements set out in condition 5.5 do not apply to any Alteration in respect of the Authorized System which:
  - 5.6.1 Is exempt under section 53(6) of the OWRA or by O. Reg. 525/98; or
  - 5.6.2 Constitutes maintenance or repair of the Authorized System.

## **6.0 Authorizations of Future Alterations for Third Pipe Collection System Additions, Modifications, Replacements and Extensions**

- 6.1 The Owner or a Prescribed Person may alter the Authorized System by adding, modifying, replacing, or extending, and operating works comprising a municipal Third Pipe Collection System to collect foundation drainage and groundwater where:
  - 6.1.1 The design of the Alteration:
    - a) Has been prepared by a Licensed Engineering Practitioner;

- b) Is limited to collection, transmission, reuse and/or treatment of only foundation drainage and groundwater, and is not designed to collect or treat sanitary Sewage;
  - c) Satisfies the Design Criteria or any municipal criteria that have been established that exceed the minimum requirements set out in the Design Criteria; and
  - d) Is scoped so that the resulting Sewage Works are intended to:
    - i Primarily function for the non-potable reuse, as deemed acceptable by the Owner and the local health unit, of foundation drainage and/or groundwater, and no discharge to a Storm Sewer or Separate Sewer if there is excess volume that cannot be reused; and/or
    - ii Provide wetland recharge, in which case, collection of rooftop runoff will also be acceptable.
- 6.1.2 The Alteration is not located on a contaminated site, or where natural occurring conditions result in contaminated discharge, or where the site receives contaminated groundwater or foundation drainage from another site, unless the discharge being received has been remediated or treated prior to acceptance by the Third Pipe Collection System.
- 6.1.3 The Owner has undertaken a site assessment for water quantity, water quality, and hydrogeological site conditions regarding the Alteration.
- 6.1.4 The Alteration will not result in Adverse Effects.
- 6.1.5 The Alteration is wholly located within the municipal boundary over which the Owner has jurisdiction or there is a written agreement in place with the adjacent property owner respecting the Alteration and resulting Sewage Works.
- 6.1.6 The Owner consents in writing to the Alteration.
- 6.1.7 A Licensed Engineering Practitioner has verified in writing that the Alteration meets the requirements of condition 6.1.1.
- 6.1.8 The Owner has verified in writing that the Alteration meets the requirements of conditions 6.1.2 to 6.1.7.
- 6.2 The consents, verifications and documentation required in conditions 6.1.7 and 6.1.8 shall be:

- 6.2.1 Recorded on Form SW3 prior to undertaking the Alteration; and
- 6.2.2 Retained for a period of at least ten (10) years by the Owner.
- 6.3 For greater certainty, the verification requirements set out in condition 6.2 do not apply to any Alteration in respect of the Authorized System which:
  - 6.3.1 Is exempt under section 53(6) of the OWRA or by O. Reg. 525/98; or
  - 6.3.2 Constitutes maintenance or repair of the Authorized System, including changes to software for an existing SCADA system resulting from Alterations authorized in condition 6.1.
- 6.4 The Owner shall update, within twelve (12) months of the Alteration of the Sewage Works being placed into service, any drawings maintained for the Municipal Stormwater Management System to reflect the Alterations of the Sewage Works, where applicable.

## **7.0 Outlets**

- 7.1 Any outlet established or altered as part of an Alteration authorized through conditions 4, 5, or 6 of Schedule D in this Approval shall have regard to the 2012 TRCA Stormwater Management Criteria document, Appendix E, for outlets.
- 7.2 Any outlet established as part of an Alteration authorized through conditions 4, 5, or 6 of Schedule D in this Approval shall not:
  - 7.2.1 Increase discharge or create a new point source discharge to privately owned land unless there is express written consent of the owner(s) of such private land(s).
  - 7.2.2 Result in Adverse Effects.

## **8.0 Previously Approved Sewage Works**

- 8.1 If approval for an Alteration to the Authorized System was issued under the EPA and is revoked by this Approval, the Owner may make the Alteration in accordance with:
  - 8.1.1 The terms of this Approval; or
  - 8.1.2 The terms and conditions of the revoked approval as of the date this approval was issued, provided that the Alteration is commenced within five (5) years of the date that the revoked approval was issued.

**9.0 Transition**

- 9.1 An Alteration of the Authorized System is exempt from the requirements in clause (e) of condition 4.1.1, clause (d) of condition 5.2.1, and clause (c) of condition 6.1.1 where:
- 9.1.1 Effort to undertake the Alteration, such as tendering or commencement of construction of the Sewage Works associated with the Alteration, begins on or before October 30, 2023.
  - 9.1.2 The design of the Alteration conforms to the Stormwater Management Planning and Design Manual, and where applicable, Design Guidelines for Sewage Works;
  - 9.1.3 The design of the Alteration was completed on or before the issue date of this Approval or a Class Environmental Assessment was completed for the Alteration and changes to the design result in significant cost increase or significant project delays; and
  - 9.1.4 The Alteration would be otherwise authorized under this Approval.

## **Schedule E: Operating Conditions**

System Owner	<b>Wilmot, The Corporation of the Township of</b>
ECA Number	<b>078-S701</b>
System Name	<b>Township of Wilmot Stormwater Management System</b>
ECA Issue Date	<b>February 8th, 2023</b>

### **1.0 General Operations**

- 1.1 The Owner shall ensure that, at all times, the Sewage Works comprising the Authorized System and the related equipment and Appurtenances used to achieve compliance with this Approval are properly operated and maintained.
- 1.2 Prescribed Persons and Operating Authorities shall ensure that, at all times, the Sewage Works under their care and control and the related equipment and Appurtenances used to achieve compliance with this Approval are properly operated and maintained.
- 1.3 In conditions 1.1 and 1.2 “properly operated and maintained” includes effective performance, adequate funding, adequate operator staffing and training, including training in applicable procedures and other requirements of this Approval and the EPA, OWRA, CWA, and regulations, adequate laboratory services, process controls and alarms and the use of process chemicals and other substances used in the Authorized System.
- 1.4 The Owner shall ensure that Sewage Works are operated with the objective that the effluent from the Sewage Works is essentially free of floating and settleable solids and does not contain oil or any other substance in amounts sufficient to create a visible film, sheen, foam, or discoloration on the receiving waters, and shall evaluate the need for maintenance if the objective is not being met.
- 1.5 The Owner shall ensure that any Storm Sewers or ditches authorized under Schedule D of this approval are not placed into operation until the associated Stormwater Management Facilities to provide treatment are constructed and operated.

### **2.0 Duties of Owners and Operating Authorities**

- 2.1 The Owner, Prescribed Persons, and any Operating Authority shall ensure the following:

- 2.1.1 At all times that the Sewage Works within the Authorized System are in service, the Sewage Works are:
- a) Operated in accordance with the requirements under the EPA and OWRA, and
  - b) Maintained in a state of good repair.
- 2.1.2 The Authorized System is operated by persons that are familiar with the requirements of this Approval.
- 2.1.3 All sampling, testing, monitoring, and reporting requirements under the EPA and this Approval that relate to the Authorized System are complied with.
- 2.1.4 All necessary steps are taken to ensure that operations of the Sewage Works and any associated physical structures do not constitute a safety or health hazard to the general public.
- 2.1.5 Where a Stormwater Management Facility ceases to function as a Stormwater Management Facility, whether by intent, accident, or otherwise (e.g., a CSO or an SSO), a workplan shall be developed that includes local community notification, plans for rehabilitating the Stormwater Management Facility to proper function in a reasonable time, identification of actions that will be taken to prevent reoccurrences, and timelines for implementing the workplan.
- 2.1.6 That operations and maintenance activities are undertaken at the frequency and in conformance with the procedures set out in the O&M Manual.
- a) A Prescribed Person or Operating Authority shall only undertake operations and maintenance activities where they have been delegated the authority to undertake such activities by the Owner or the Owner has expressly approved the activity(ies).
- 2.2 For clarity, the requirements outlined in the above conditions 2.1 for Prescribed Persons and any Operating Authority only apply to Sewage Works within the Authorized System where they are responsible for the operation.
- 2.3 The Owner, Prescribed Persons, and Operating Authority shall take all reasonable steps to minimize and ameliorate any Adverse Effect on the Natural Environment or impairment of the quality of water of any waters resulting from the operation of the Authorized System, including such accelerated or additional monitoring as may be necessary to determine the nature and extent of the effect or impairment.



### 3.0 Operations and Maintenance

#### 3.1 Inspection

- 3.1.1 The Owner shall ensure that all Sewage Works within the Authorized System are inspected at the frequency and in accordance with procedures set out in their O&M Manual.
- 3.1.2 The owner shall ensure that:
- a) Any Stormwater Management Facilities, pumping stations, and any outlets that discharge to a receiver, are inspected at least once before December 31, 2027, if these have not been inspected since January 1, 2018 and thereafter as required by the O&M Manual; and
  - b) Any Stormwater Management Facilities, pumping stations, and any outlets that discharge to a receiver, established, or replaced within the Authorized System after the date of issuance of this Approval, are inspected within one year of being placed into service and thereafter as required by the O&M Manual.
- 3.1.3 The Owner shall clean and maintain Sewage Works within the Authorized System to ensure the Sewage Works perform as designed.
- 3.1.4 The Owner shall inspect the Stormwater Management Facilities in the Authorized System after significant flooding events as defined in, and in accordance with procedures documented in, the O&M Manual.
- 3.1.5 The Owner shall maintain records of the results of the inspections required in condition 3.1.1, 3.1.2 and 3.1.4 and any cleaning and maintenance operations undertaken, and shall make available the records for inspection by the Ministry upon request. The records shall include the following:
- a) Asset ID and name of the Sewage Works;
  - b) Date and results of each inspection, maintenance, or cleaning;
  - c) Name of person who conducted the inspection, maintenance, or the name of the inspecting official, where applicable, and
  - d) As applicable to the type of works, observations resulting from the inspection including, at a minimum:

- i Hydraulic operation of the works (e.g., length of occurrence since the last rainfall event, evidence or occurrence of overflows).
- ii Condition of vegetation in and around the works.
- iii Occurrence of obstructions at the inlet and outlet of the works.
- iv Evidence of spills and/or oil/grease contamination.
- v Presence of trash build-up, and
- vi Measurements of other parameters as required in the Monitoring Plan.

### 3.2 Operations & Maintenance (O&M) Manual

3.2.1 The Owner shall prepare and implement an operations and maintenance manual for Sewage Works within the Authorized System on or before October 31, 2024, that includes or references, but is not necessarily limited to, the following information:

- a) Procedures for the routine operation of the Sewage Works;
- b) Inspection programs, including the frequency of inspection, and the methods or tests employed to detect when maintenance is necessary, including:
  - i Presence of algae and/or invasive species impairing the Works (e.g., phragmites, goldfish);
  - ii Measurements of sediment depth, manual water levels (staff gauge) and/or visual observations, as appropriate to the Stormwater Management Facilities.
- c) Maintenance and repair programs, including:
  - i The frequency of maintenance and repair for the Sewage Works;
  - ii Stormwater pond sediment cleanout, dewatering, and management;

- iii Excavation, modification, replacement of LID soil/media/aggregate/geotextile, such as bioretention cells, green roof, permeable pavement; and
      - iv The frequency of maintenance for any other Stormwater Management Facilities identified in Schedule B that collect sediment.
  - d) Operational and maintenance requirements to protect sources of drinking water, such as those included in the Standard Operating Policy for Sewage Works, and any applicable local Source Protection Plan policies;
  - e) Procedures for routine physical inspection and calibration of monitoring equipment or components in accordance with the Monitoring Plan;
  - f) Emergency Response, Spill Reporting and Contingency Plans and Procedures for dealing with equipment breakdowns, potential spills, and any other abnormal situations, including notification to the Spills Action Centre, the Medical Officer of Health, and the District Manager, as applicable;
  - g) Procedures for receiving, responding, and recording public complaints, including recording any follow-up actions taken; and
  - h) As-built drawings or record drawings of the Sewage Works for stormwater works constructed on or after January 1, 2010 and where available for stormwater works constructed prior to January 1, 2010.
- 3.2.2 The Owner shall review and update the O&M Manual and ensure that access to a copy is readily available for each Stormwater Management Facility for the operational life of the works.
- 3.2.3 The Owner shall provide a copy of the O&M Manual to Ministry staff, upon request.
- 3.2.4 The Owner shall revise the O&M Manual to include procedures necessary for the operation and maintenance of any Sewage Works within the Authorized System that are established, altered, extended, replaced, or enlarged after the date of issuance of this approval prior to placing into service those Sewage Works.
- 3.2.5 For greater certainty, the O&M Manual may be a single document or a collection of documents that, when considered together, apply to all parts of the Authorized System.

- 3.3 On or before October 31, 2026, the Owner shall establish signage to notify the public at any Stormwater Management Facility identified in Schedule B that is a wet pond, dry pond, hybrid Facility, or engineered wetland. The signage shall include the following minimum information:
- 3.3.1 Identification that the site contains a Stormwater Management Facility;
  - 3.3.2 Identification of potential hazards and limitations of water use, as applicable;
  - 3.3.3 Identification of the purpose of the Facility;
  - 3.3.4 ECA approval number and/or asset ID; and
  - 3.3.5 Owner's contact information.
- 3.4 Prior to any maintenance of Sewage Works comprising the Authorized System, the Owner shall ensure that all applicable permits or authorizations have been obtained from Federal or Provincial agencies having legislative mandates relating to species at risk or water resources.

#### **4.0 Monitoring Plan**

- 4.1 On or before October 31, 2025 or within twenty-four (24) months of the date of the publication of the Ministry's monitoring guidance, whichever is later, the Owner shall develop and implement a monitoring plan for the Authorized System. The monitoring plan shall be:
- 4.1.1 Signed and approved by management with the authority delegated by the Owner to do so;
  - 4.1.2 Peer-reviewed by a third-party Qualified Person (QP), external to the development of the Monitoring Plan, to verify the adequacy of the Monitoring Plan in complying with conditions 4.4 and 4.5 of Schedule E. The results of the peer review shall include:
    - a) Written confirmation from the QP that they have the experience and qualifications to carry out the work; and
    - b) Written confirmation from the QP of the adequacy of the Monitoring Plan.
- 4.2 The Owner, or a QP designated by the Owner, may jointly develop the Monitoring Plan in partnership with Owner(s) of other Municipal Stormwater Management Systems as long as the Municipal Stormwater Management Systems are within the same watershed.

- 4.3 The Owner shall ensure the Monitoring Plan is implemented and any resulting monitoring data is recorded in an electronic database.
- 4.4 The Monitoring Plan shall include:
- 4.4.1 Procedures to verify that the operational performance of the Authorized System is as designed/planned;
  - 4.4.2 Procedures to assess the environmental impact of the Municipal Stormwater Management System; and
  - 4.4.3 Procedures for any corrective action that may be required to address any performance deficiencies or environmental impacts identified from above conditions 4.4.1 or 4.4.2.
- 4.5 The Monitoring Plan shall also include, but not be limited to:
- 4.5.1 Identification of the Sewage Works to be monitored, including outlets and any works that provide quality and/or quantity control;
  - 4.5.2 Identification of the key receivers to be monitored within the Owner's municipal boundaries and the monitoring locations;
  - 4.5.3 Consideration of relevant municipal land use and environmental planning documents (e.g., Stormwater Management Master Plan, Class Environmental Assessment Project, asset management plan, subwatershed studies, and planned development);
  - 4.5.4 Characterization of water quality and quantity conditions and identification of water users to be protected, based on conditions 4.5.2 and 4.5.3;
  - 4.5.5 Identification of water quality and quantity goals, as it relates to Stormwater management, using the information collected in condition 4.5.4;
  - 4.5.6 Identification of locations of rainfall gauges to be used;
  - 4.5.7 Identification of inspections, measurements, sampling, analysis and/or other monitoring activities that were used as the basis for or will inform future updates to the procedures identified in condition 4.4.
  - 4.5.8 Details respecting a monitoring program for the works and the receivers, that includes, at a minimum:
    - a) Hydrological, chemical, physical, and biological parameters, as appropriate, in alignment with the goals;

- b) Ensures water level of the Stormwater Measurement Facilities, excluding MTDs, are measured at regular intervals with a water level gauge;
  - c) Monitoring methodology, including the frequency and protocols for sampling, analysis, and recording, with consideration of dry and wet weather events and timing of sampling during wet weather events.
  - d) Ensures that the time of all samples or measurements are recorded.
- 4.5.9 An implementation plan for the monitoring program that identifies timelines and, if the monitoring occurs on a rotational basis, provides a description of the rotational schedule and associated works.
- 4.5.10 Includes a summary of all monitoring data along with an interpretation of the data and any conclusion drawn from the data evaluation about the need for future modifications to the Authorized System or system operations, and
- 4.5.11 Consideration of adaptive management practices (e.g., evidence-based decision making).
- 4.6 The Owner shall ensure that the Monitoring Plan is updated where necessary within twelve (12) months of any Alteration to the Authorized System, or more frequently as required by the Monitoring Plan.
- 4.7 The Owner shall, on request and without charge, provide a copy of the Monitoring Plan and any resulting monitoring data to members of the public.

## **5.0 Reporting**

- 5.1 The Owner shall, upon request, make all manuals, plans, records, data, procedures and supporting documentation available to Ministry staff.
- 5.2 The Owner shall prepare an annual performance report for the Authorized System that:
- 5.2.1 Is submitted to the Director on or before April 30<sup>th</sup> of each year and covers the period from January 1<sup>st</sup> to December 31<sup>st</sup> of the preceding calendar year.
    - a) For clarity, the first report shall cover the period of January 1, 2024 to December 31<sup>st</sup>, 2024 and be submitted to the Director on or before April 30<sup>th</sup>, 2025.

- 5.2.2 Includes a summary of all monitoring data along with an interpretation of the data and an overview of the condition and operational performance of the Authorized System and any Adverse Effects on the Natural Environment;
  - 5.2.3 Includes a summary and interpretation of environmental trends based on all monitoring information and data for the previous five (5) years;
  - 5.2.4 Includes a summary of any operating problems encountered and corrective actions taken;
  - 5.2.5 Includes a summary of all inspections, maintenance, and repairs carried out on any major structure, equipment, apparatus, mechanism, or thing forming part of the Authorized System;
  - 5.2.6 Includes a summary of the calibration and maintenance carried out on all monitoring equipment;
  - 5.2.7 Includes a summary of any complaints related to the Sewage Works received during the reporting period and any steps taken to address the complaints;
  - 5.2.8 Includes a summary of all Alterations to the Authorized System within the reporting period that are authorized by this Approval including a list of Alterations that pose a Significant Drinking Water Threat;
  - 5.2.9 Includes a summary of all spills or abnormal discharge events;
  - 5.2.10 Includes a summary of actions taken, including timelines, to improve or correct performance of any aspect of the Authorized System; and
  - 5.2.11 Includes a summary of the status of actions for the previous reporting year.
- 5.3 The report described in condition 5.2 shall be:
- 5.3.1 Made available, on request and without charge, to members of the public who are served by the Authorized System; and
  - 5.3.2 Made available, by June 1<sup>st</sup> of the same reporting year, to members of the public without charge by publishing the report on the Internet, if the Owner maintains a website on the Internet.

## 6.0 Record Keeping

- 6.1 The Owner shall retain for a minimum of ten (10) years from the date of their creation:
- 6.1.1 All records, reports and information required by this Approval and related to or resulting from Alterations to the Authorized System, and
  - 6.1.2 All records, report and information related to the operation, maintenance and monitoring activities required by this Approval.
- 6.2 The Owner shall update, within twelve (12) months of any Alteration to the Authorized System being placed into service, any drawings maintained for the Municipal Stormwater Management System to reflect the Alteration of the Sewage Works, where applicable.

## **7.0 Review of this Approval**

- 7.1 No later than the date specified in Condition 1 of Schedule A of this Approval, the Owner shall submit to the Director an application to have the Approval reviewed. The application shall, at minimum:
- 7.1.1 Include an updated description of the Sewage Works within the Authorized System, including any Alterations to the Sewage Works that were made since the Approval was last issued; and
  - 7.1.2 Be submitted in the manner specified by Director and include any other information requested by the Director.

## **8.0 Source Water Protection**

- 8.1 The Owner shall ensure that any Alteration in the Authorized System is designed, constructed, and operated in such a way as to be protective of sources of drinking water in Vulnerable Areas as identified in the Source Protection Plan, if available.
- 8.2 The Owner shall prepare a "Significant Drinking Water Threat Assessment Report for Proposed Alterations" for the Authorized System on or before October 31, 2024 that includes, but is not necessarily limited to:
- 8.2.1 An outline of the circumstances under which proposed Alterations could pose a Significant Drinking Water Threat based on the Director's Technical Rules established under the CWA.
  - 8.2.2 An outline of how the Owner assesses the proposed Alterations to identify drinking water threats under the CWA.



- 8.2.3 For any proposed Alteration a list of components, equipment, or Sewage Works that are being altered and have been identified as a Significant Drinking Water Threat.
- 8.2.4 A summary of design considerations and other measures that have been put into place to mitigate risks resulting from construction or operation of the components, equipment, or Sewage Works identified in condition 8.2.3, such as those included in the Standard Operating Policy for Sewage Works.
- 8.3 The Owner shall make any necessary updates to the report required in condition 8.2 at least once every twelve (12) months.
- 8.4 Any components, equipment, or Sewage Works added to the report required in condition 8.2 shall be included in the report for the operational life of the Sewage Works.
- 8.5 Upon request, the Owner shall make a copy of the report required in condition 8.2 available to the Ministry or Source Protection Authority staff.

## 9.0 Storm Sewer Catchment Asset Inventory

- 9.1 The Owner shall prepare and submit to the Director an inventory of the storm sewersheds and classify in accordance with Tables E1 and E2, on or before October 31, 2026. Minimum classification of the level of Stormwater management is as follows:
- 9.1.1 Level A – Stormwater receives treatment for water quality and quantity prior to discharge to the environment;
- 9.1.2 Level B – Stormwater receives treatment for water quality but no water quantity prior to discharge to the environment; and
- 9.1.3 Level C – Stormwater receives no treatment for water quality prior to discharge to the environment.

Outlet Asset ID	Sewershed Catchment Area (ha)	Tributary or Receiver	Subwatershed/ Watershed	Stormwater Management Level (A, B or C)	Treatment provided by other municipality (if applicable)

Stormwater Management Level	Total Number of Outlets to Environment	Total Sewershed Catchment Area (ha)

Level A		
Level B		
Level C		

9.2 Within 12 (twelve) months of the date that the inventory required in condition 9.1 is submitted to the Director, the document(s) or file(s) referenced in Table B1 of Schedule B of this Approval shall be updated to identify the storm sewersheds for each outlet and their level of Stormwater management.

## Schedule F: Residue Management

System Owner	Wilmot, The Corporation of the Township of
ECA Number	078-S701
System Name	Township of Wilmot Stormwater Management System
ECA Issue Date	February 8th, 2023

### 1.0 Residue Management System

1.1 Not Applicable.

## Appendix A – Stormwater Management Criteria

### 1.0 Applicability of Criteria

- 1.1 The criteria listed under Table A1 of this Appendix applies to all drainage areas greater than 0.1 ha, with the construction erosion and sediment control criteria applying also to sites <0.1 ha;
- 1.2 Despite condition 1.1 of Appendix A, if some or all of the criteria listed under Table A1 of this Appendix have been assessed for and addressed in other adjacent developed lands to the project site through a subwatershed plan or equivalent study, then those criteria may not be applicable to the project site.

**Table A1. Performance Criteria**

<b>Water Balance</b> <sup>[1]</sup>	<p><b>FOR DEVELOPMENT SCENARIOS</b> <sup>[2]</sup></p> <p><b>Assessment Studies:</b></p> <p>i) Control <sup>[3]</sup> as per the criteria identified in the water balance assessment completed in one or more of the following studies <sup>[15]</sup>, if undertaken: a watershed/subwatershed plan; Source Protection Plan (Assessment Report component); Master Stormwater Management Plan, Master Environmental Servicing Plan; Class EA, or similar approach that transparently considers social, environmental and financial impacts; or local site study including natural heritage, Ecologically significant Groundwater Recharge Areas (EGRA), inflow and infiltration strategies. The assessment should include sufficient detail to be used at a local site level and consistent with the various level of studies; OR</p> <p><b>IF Assessment Studies in i) NOT completed:</b></p> <p>ii) Control <sup>[3]</sup> the recharge <sup>[4]</sup> to meet Pre-development <sup>[5]</sup> conditions on property; <b>OR</b></p> <p>iii) Control <sup>[3]</sup> the runoff from the 90<sup>th</sup> percentile storm event.</p> <p><b>Lake Simcoe Watershed Municipalities:</b></p> <p>iv) Control <sup>[3]</sup> as per the evaluation of anticipated changes in water balance between Pre-development and post-development assessed through a Stormwater management plan in support of an application for Major Development <sup>[6]</sup>. The assessment should include sufficient detail to be used at a local site level. If it is demonstrated, using the approved water balance estimation methods <sup>[7]</sup>, that the site’s post to Pre-development water balance cannot be met, and Maximum Extent Possible <sup>[8]</sup> has been attained, the proponent may use Lake Simcoe and Region Conservation Authority’s (LSRCA) Recharge Compensation Program <sup>[9]</sup>.</p> <p><b>FOR RETROFIT SCENARIOS</b> <sup>[10]</sup></p> <p><b>Assessment Studies:</b></p> <p>i) Control as per criteria identified in the water balance assessment completed in one or more of the following studies: a watershed/subwatershed plan, Source Protection Plan (Assessment Report component), Master Stormwater Management Plan, Master Environmental Servicing Plan,</p>
-------------------------------------	--

	<p>Class EA, or local site study including natural heritage, EGRA, inflow and infiltration strategies, if undertaken. The assessment should include sufficient detail to be used at a local site level and consistent with the various level of studies; <b>OR</b></p> <p>ii) If constraints <sup>[11]</sup> identified in i), then control <sup>[3]</sup> as per Maximum Extent Possible <sup>[8]</sup> based on environmental site feasibility studies or address local needs<sup>[14]</sup>.</p> <p><b>IF Assessment Studies in i) NOT completed:</b></p> <p>iii) Control <sup>[3]</sup> the recharge <sup>[4]</sup> to meet Pre-development <sup>[5]</sup> conditions on property; <b>OR</b></p> <p>iv) Control <sup>[3]</sup> the runoff from the 90<sup>th</sup> percentile storm event.</p>
<p><b>Water Quality</b> <sup>[1]</sup></p>	<p><b>FOR DEVELOPMENT SCENARIOS</b> <sup>[2]</sup></p> <p>All of the following criteria must be met for development scenarios:</p> <p><b>General:</b></p> <p>i) Characterize the water quality to be protected and Stormwater Contaminants (e.g., suspended solids, nutrients, bacteria, water temperature) for potential impact on the Natural Environment, and control as necessary, <b>OR</b></p> <p>ii) As per the watershed/subwatershed plan, similar area-wide Stormwater study, or Stormwater management plan to minimize, or where possible, prevent increases in Contaminant loads and impacts to receiving waters.</p> <p><b>Suspended Solids:</b></p> <p>i) Control <sup>[3]</sup> 90<sup>th</sup> percentile storm event and if conventional methods are necessary, then enhanced, normal, or basic levels of protection (80%, 70%, or 60% respectively) for suspended solids removal (based on the receiver).</p> <p><b>Phosphorus:</b></p> <p>i) Minimize existing phosphorus loadings to Lake Erie and its tributaries, as compared to 2018 or conditions prior to the proposed development, <b>OR</b></p> <p>ii) Minimize phosphorus loadings to Lake Simcoe and its tributaries. Proponents with development sites located in the Lake Simcoe watershed shall evaluate anticipated changes in phosphorus loadings between Pre-development and post-development through a Stormwater management plan in support of an application for Major Development <sup>[6]</sup>. The assessment should include sufficient detail to be used at a local site level. If, using the approved phosphorus budget tool <sup>[12]</sup>, it is demonstrated that the site’s post to Pre-development phosphorus budget cannot be met, and Maximum Extent Possible <sup>[8]</sup> has been attained, the proponent may use LSRCA’s Phosphorus Offsetting Policy <sup>[9]</sup>.</p> <p><b>FOR RETROFIT SCENARIOS</b> <sup>[10]</sup></p> <p>i) Improve the level of water quality control currently provided on site; <b>AND</b></p> <p>ii) As per the ‘Development’ criteria for Suspended Solids, <b>OR</b></p> <p>iii) <b>If ‘Development’ criteria for Suspended Solids cannot be met</b>, Works are designed as a multi-year retrofit project, in accordance with a rehabilitation study or similar area-wide Stormwater study, such that the completed treatment train will achieve the ‘Development’ criteria for Suspended Solids or local needs<sup>[14]</sup>, within ten (10) years; <b>OR</b></p>

<p><b>Erosion Control (Watershed)</b> <sup>[1]</sup></p>	<p>iv) If constraints <sup>[11]</sup> identified in ii) and iii), then control <sup>[3]</sup> as per Maximum Extent Possible <sup>[8]</sup> based on environmental site feasibility studies.</p> <p><b>FOR DEVELOPMENT SCENARIOS</b> <sup>[8]</sup></p> <p>i) As per erosion assessment completed in watershed/subwatershed plan, Master Stormwater Management Plan, Master Environmental Servicing Plan, Drainage Plan, Class EA, local site study, geomorphologic study, or erosion analysis; <b>OR</b></p> <p>ii) As per the Detailed Design Approach or Simplified Design Approach methods described in the Stormwater Management Planning and Design Manual:</p> <p>a. The Detailed Design Approach may be selected by the proponent for any development regardless of size and location within the watershed provided technical specialists are available for the completion of the technical assessments; or considered more appropriate than the simplified approach given the size and location of the development within the watershed and the sensitivity of the receiving waters in terms of morphology and habitat function.</p> <p>b. The Simplified Design Approach may be adopted for watersheds whose development area is generally less than twenty hectares AND either one of the following two conditions apply:</p> <p>1) The catchment area of the receiving channel at the point-of-entry of Stormwater drainage from the development is equal to or greater than twenty-five square kilometres; or</p> <p>2) Meets the following conditions:</p> <ul style="list-style-type: none"> <li>• The channel bankfull depth is less than three quarters of a metre;</li> <li>• The channel is a headwater stream;</li> <li>• The receiving channel is not designated as an Environmentally Sensitive Area (ESA) or Area of Natural or Scientific Interest (ANSI) and does not provide habitat for a sensitive aquatic species;</li> <li>• The channel is stable to transitional; and</li> <li>• The channel is slightly entrenched; <b>OR</b></li> </ul> <p>iii) In the absence of a guiding study, detain at minimum, the runoff volume generated from a 25 mm storm event over 24 to 48 hours.</p> <p><b>FOR RETROFIT SCENARIOS</b> <sup>[10]</sup></p> <p>i) If approaches i-iii) under ‘Development Scenarios’ are not feasible as per identified constraints <sup>[11]</sup>, then improve the level of erosion control <sup>[3]</sup> currently provided on site to Maximum Extent Possible <sup>[8]</sup> based on environmental site feasibility studies or address local needs<sup>[14]</sup>.</p>
<p><b>Water Quantity (Minor and Major System)</b> <sup>[1]</sup></p>	<p>i) As per municipal standards, Master Stormwater Management Plan, Class EA, Individual EA and/or ECA, as appropriate for the type of project <sup>[13]</sup></p>
<p><b>Flood Control (Watershed Hydrology)</b> <sup>[1]</sup></p>	<p><b>FOR DEVELOPMENT SCENARIOS</b> <sup>[2]</sup></p> <p>i) Manage peak flow control as per watershed/subwatershed plans, municipal criteria being a minimum 100 year return storm (except for site-specific considerations and proximity to receiving water bodies), municipal guidelines and standards, Individual/Class EA, ECA, Master Plan, as appropriate for the type of project <sup>[13]</sup>.</p>

	<p><b>FOR RETROFIT SCENARIOS</b> <sup>[10]</sup></p> <p>i) If approaches i) under ‘Development Scenarios’ are not feasible as per identified constraints <sup>[11]</sup>, then improve the level of flood control <sup>[3]</sup> currently provided on site to Maximum Extent Possible <sup>[8]</sup> based on environmental site feasibility studies.</p>
<p><b>Construction Erosion and Sediment Control</b></p>	<p>i) Manage construction erosion and sediment control through development and implementation of an erosion and sediment control (ESC) plan. The ESC plan shall:</p> <ul style="list-style-type: none"> <li>a. Have regard to Canadian Standards Association (CSA) W202 Erosion and Sediment Control Inspection and Monitoring Standard (as amended); OR</li> <li>b. Have regard to Erosion and Sediment Control Guideline for Urban Construction 2019 by TRCA (as amended).</li> </ul> <p>ii) Be prepared by a QP for sites with drainage areas greater than 5 ha or if specified by the Owner for a drainage lower than 5 ha.</p> <p>iii) Installation and maintenance of the ESC measures specified in the ESC plan shall have regard to CSA W208:20 Erosion and Sediment Control Installation and Maintenance (as amended).</p> <p>iv) For sites with drainage areas greater than 5 ha, a QP shall inspect the construction ESC measures, as specified in the ESC plan.</p>
<p><b>Footnote</b></p>	<ol style="list-style-type: none"> <li>1. Where the opportunity exists on your project site or the same subwatershed, reallocation of development elements may be optimal for management as described in footnote <sup>[3]</sup>.</li> <li>2. Development includes new development, redevelopment, infill development, or conversion of a rural cross-section into an urban cross-section.</li> <li>3. Stormwater volumes generated from the geographically specific 90th percentile rainfall event on an annual average basis from all surfaces on the entire site are targeted for control. Control is in the following hierarchical order, with each step exhausted before proceeding to the next: 1) retention (infiltration, reuse, or evapotranspiration), 2) LID filtration, and 3) conventional Stormwater management. Step 3, conventional Stormwater management, should proceed only once Maximum Extent Possible <sup>[8]</sup> has been attained for Steps 1 and 2 for retention and filtration.</li> <li>4. Recharge is the infiltration and movement of surface water into the soil, past the vegetation root zone, to the zone of saturation, or water table.</li> <li>5. Pre-development is defined as the more stringent of the two following scenarios: 1) a site’s existing condition, or 2) as defined by the local municipality.</li> <li>6. Major Development has the same meaning as in the Lake Simcoe Protection Plan, 2009.</li> <li>7. Currently, the approved tool by LSRCA for calculating the water balance is the Thornthwaite-Mather Method. Other tools agreed upon by relevant approval agencies (e.g., LSRCA, municipality, or Ministry) may also be acceptable, subject to written acceptance by the Director.</li> <li>8. Maximum Extent Possible means maximum achievable Stormwater volume control through retention and LID filtration engineered/landscaped/technical Stormwater practices, given the site constraints <sup>[11]</sup>.</li> <li>9. Information pertaining to LSRCA’s Recharge Compensation Program and Phosphorus Offsetting Policy is available on LSRCA’s website (lsrca.on.ca), or in “Water Balance Recharge Policy for the Lake Simcoe Protection Plan”, dated July 2021, and prepared by Lake Simcoe Region Conservation Authority and “Phosphorus Offsetting Policy”, dated July 2021, and prepared by Lake Simcoe Region Conservation Authority.</li> </ol>

	<p>10. Retrofit means: 1) a modification to the management of the existing infrastructure, 2) changes to major and minor systems, or 3) adding Stormwater infrastructure, in an existing area on municipal right-of-way, municipal block, or easement. It does not include conversion of a rural cross-section into an urban cross-section.</p> <p>11. Site constraints must be documented. A list of site constraints can be found in Table A2.</p> <p>12. Tools for calculating phosphorus budgets may include the Ministry’s Phosphorus Tool, the Low Impact Development Treatment Train Tool developed in partnership by TRCA, LSRCA, and Credit Valley Conservation (CVC), or other tools agreed upon by the LSRCA and other relevant approval agencies including the municipality.</p> <p>13. Possible to look at combined grey infrastructure and LID system capacity jointly.</p> <p>14. Local needs include requirements for water quality, erosion, and/or water balance retrofits identified by the owner through ongoing operation and maintenance of the stormwater system, including inspection of local receiving systems and the characterization of issues requiring remediation through retrofit controls.</p> <p>15. All studies shall conform with Ministry policies. If any conclusions in the studies negate policy, then the project will require a direct submission to the Ministry for review through an application pertaining to a Schedule C Notice.</p>
--	---

**Table A2. Stormwater Management Practices Site Constraints**

Site Constraints	
a)	Shallow bedrock <sup>[1]</sup> , areas of blasted bedrock <sup>[2]</sup> , and Karst;
b)	High groundwater <sup>[1]</sup> or areas where increased infiltration will result in elevated groundwater levels which can be shown through an appropriate area specific study to impact critical utilities or property (e.g., susceptible to flooding);
c)	Swelling clays <sup>[3]</sup> or unstable sub-soils;
d)	Contaminated soils (e.g., brownfields);
e)	High Risk Site Activities including spill prone areas;
f)	Prohibitions and or restrictions per the approved Source Protection Plans and where impacts to private drinking water wells and /or Vulnerable Domestic Well Supply Areas cannot be appropriately mitigated;
g)	Flood risk prone areas or structures and/ or areas of high inflow and infiltration (I/I) where wastewater systems (storm and sanitary) have been shown through technical studies to be sensitive to groundwater conditions that contribute to extraneous flow rates that cause property flooding / Sewer back-ups;
h)	For existing municipal rights-of-way infrastructure (e.g., roads, sidewalks, utility corridor, Sewers, LID, and trails) where reconstruction is proposed and where surface and subsurface areas are not available based on a site-specific assessment completed by a QP;
i)	For developments within partially separated wastewater systems where reconstruction is proposed and where, based on a site-specific assessment completed by a QP, can be shown to: <ul style="list-style-type: none"> <li>i Increase private property flood risk liabilities that cannot be mitigated through design;</li> <li>ii Impact pumping and treatment cost that cannot be mitigated through design; or</li> </ul>



iii	Increase risks of structural collapse of Sewer and ground systems due to infiltration and the loss of pipe and/or pavement support that cannot be mitigated through design.
j)	Surface water dominated or dependent features including but not limited to marshes and/or riparian forest wetlands which derive all or a majority of their water from surface water, including streams, runoff, and overbank flooding. Surface water dominated or dependent features which are identified through approved site specific hydrologic or hydrogeologic studies, and/or Environmental Impact Statements (EIS) may be considered for a reduced volume control target. Pre-consultation with the MECP and local agencies is encouraged;
k)	Existing urban areas where risk to water distribution systems has been identified through assessments to meet applicable drinking water requirements, including Procedures F-6 and F-6-1, and substantiated by a QP through an appropriate area specific study and where the risk cannot be reasonably mitigated per the relevant design guidelines;
l)	Existing urban areas where risk to life, human health, property, or infrastructure has been identified and substantiated by a QP through an appropriate area specific study and where the risk cannot be reasonably mitigated per the relevant design guidelines;
m)	Water reuse feasibility study has been completed to determine non-potable reuse of Stormwater for onsite or shared use;
n)	Economic considerations set by infrastructure feasibility and prioritization studies undertaken at either the local/site or municipal/system level <sup>[4]</sup> .
<b>Footnote:</b>	
<ol style="list-style-type: none"> <li>1. May limit infiltration capabilities if bedrock and groundwater is within 1m of the proposed Facility invert per Table 3.4.1 of the LID Stormwater Planning and Design Guide (2010, V1.0 or most recent by TRCA/CVC). Detailed assessment or studies are required to demonstrate infiltration effects and results may permit relaxation of the minimum 1m offset.</li> <li>2. Where blasting is more localized, this constraint may not be an issue elsewhere on the property. While infiltration-based practices may be limited in blasted rock areas, other forms of LID, such as filtration, evapotranspiration, etc., are still viable options that should be pursued.</li> <li>3. Swelling clays are clay soils that is prone to large volume changes (swelling and shrinking) that are directly related to changes in water content.</li> <li>4. Infrastructure feasibility and prioritization studies should comprehensively assess Stormwater site opportunities and constraints to improve cost effectiveness, environmental performance, and overall benefit to the receivers and the community. The studies include assessing and prioritizing municipal infrastructure for upgrades in a prudent and economically feasible manner.</li> </ol>	