




Building
Division

Deck Layout and Span Tables

DATE:

SCALE:
NOT TO SCALE

DRAWING NO.:



Deck Layout

****All decking is to be 5/4 x 6 wood material or approved equal**

Maximum 2-Ply Beam Length			
Supported Joist Length	2 x 8	2 x 10	2 x 12
4'-0"	11'-7"	14'-10"	17'-4"
6'-0"	9'-10"	12'-1"	14'-0"
8'-0"	8'-7"	10'-6"	12'-3"
10'-0"	7'-8"	9'-4"	10'-8"
Maximum 3-Ply Beam Length			
8'-0"	10'-8"	13'-0"	15'-1"
10'-0"	9'-6"	11'-8"	13'-6"

Maximum Floor Joist Length		
Joist Size	Max. Span	Max. Cantilever
2x8 @ 12" O.C.	12'-6"	20"
2x8 @ 16" O.C.	11'-9"	16"
2x8 @ 24" O.C.	11'-0"	14"
2x10 @ 12" O.C.	14'-6"	28"
2x10 @ 16" O.C.	13'-8"	24"
2x10 @ 24" O.C.	12'-10"	20"
2x12 @ 12" O.C.	16'-5"	28"
2x12 @ 16" O.C.	15'-6"	24"
2x12 @ 24" O.C.	14'-6"	20"

* Install solid blocking when floor joist span exceeds 6'-10". Blocking required to be of the same material and size as the floor joist and located not more than 6'-10" from each support and other rows of blocking.



Building Division

Deck Details


Guard, Post, Beam, Footing and Ledger Board

DATE:


SCALE:
NOT TO SCALE

DRAWING NO.:

MIN. GUARD HEIGHT
WITH DECKS:
- 5'-11" OR LESS
ABOVE GROUND = 35"
- MORE THAN 5'-11"
ABOVE GROUND = 42"




Option A



Option B

NOTE: ANYTHING OTHER
THAN A WOOD GUARD/
RAILING, PLEASE SUBMIT
A COPY OF THE
PRE-ENGINEERED
GAURD/RAILING DETAILS
WITH YOUR BUILDING
APPLICATION.


Guard Details




Post Detail

**SOLID BLOCKING REQUIRED FOR BEAMS @ 18" O.C.

**ADDITIONAL LATERAL BRACING MAY BE REQUIRED. CONFIRM
WITH BUILDING INSPECTOR @ FRAMING INSPECTION.



Guard Post Detail



MINIMUM 1/2"Ø ANCHOR BOLTS @ 16" CENTERS
STAGGERED. ANCHOR BOLTS MUST BE INTO
WOOD FRAMING OR FOUNDATION WALL. DO
NOT SECURE INTO BRICK VENEER ALONE.

Ledge Board Detail




Building Division

Deck Elevations and Details

DATE:

SCALE:
NOT TO SCALE

DRAWING NO.:




Deck Elevation

Sonotube Sizes

Diameter	*Weight
8"Ø	1047 lbs
10"Ø	1635 lbs
12"Ø	2355 lbs
14"Ø	3207 lbs
16"Ø	4189 lbs

*Weight = (supported joist length each side of post x half beam length each side of post) x 40 lbs/SF

- 35" FOR DECKS 5'-11" OR LESS ABOVE GRADE
- 42" FOR DECKS GREATER THAN 5'-11" ABOVE GRADE.



Stair Detail

PRIVATE STAIRS:
MAX. RISE 7-7/8"
MIN. RISE 5"
MAX. RUN 14"
MIN. RUN 10"
MAX TREAD 14"
MIN TREAD 11"
max 1" nosing

*Risers shall have a uniform height in any one flight of stairs.
*Treads shall have a uniform run and tread depth in any one flight of stairs.

DECK NOTES

Footings:


- Footings to be concrete filled sonotubes extending a minimum of 4'-0" below grade and 6" above grade. See the minimum diameters noted on the drawing.
- All footings to bear on undisturbed soil.

Columns:

- Minimum column size:
4"x4" for decks < 4'-0" above grade
6"x6" for decks > 4'-0" above grade

Beam/Joist Framing:

- 2x__ ledger board fastened to the house wood structure, NOT the brick veneer, with minimum 3/8"Ø bolts @ 16" o.c. staggered.
- If the beam is fastened on each side of the column, provide solid blocking @ 18" o.c. between plys of the beam.
- Max ____" joist cantilever.
- Max ____" beam cantilever.
- Joist hanger nails shall be used to attach all joist hangers. Do not use screws.
- Where the joists span > 6'-10", provide solid blocking at mid span (6'-10" o.c. max.)



TYPICAL LEDGER BOARD BOLT LENGTHS:

Siding - Minimum 8"

Concrete - Minimum 6" Sleeve Anchor

Brick - Minimum 10"

For other types of cladding, verify minimum bolt length with inspector prior to installation. The bolt must be able to be tightened without withdrawing. Both Lag Bolts and Lag Screws are permitted.

GUARD/RAILING NOTES:

- Guard posts are not permitted to be notched or sit outside the rim joist
- The maximum post spacing is 5'-1" for pressure treated S.P.F. guard posts.
- Minimum guard height:
36" for decks < 5'-11" above grade
42" for decks > 5'-11" above grade

IT IS THE CONTRACTOR'S RESPONSIBILITY TO ENSURE THAT ALL CONSTRUCTION CONFORMS TO THE REQUIREMENTS OF THE ONTARIO BUILDING CODE. NOTATIONS MADE ON THESE DRAWINGS ARE FOR YOUR INFORMATION AND ASSISTANCE ONLY AND DO NOT NECESSARILY COMMENT ON ALL AREAS OF CONSTRUCTION.

ALL GUARDS MUST BE NON-CLIMBABLE WITH NO HORIZONTAL MEMBERS BETWEEN 5 1/2" AND 35" ABOVE THE FLOOR OR WALKING SURFACE.

THE ONTARIO BUILDING CODE REQUIRES THAT A COPY OF THE DRAWINGS ARE SPECIFICATIONS THAT HAVE BEEN REVIEWED BY OUR DEPARTMENT BE KEPT AT THE CONSTRUCTION SITE AT ALL TIMES.

PRIVATE STAIRS :

MAX. RISE 7 7/8"
MIN. RISE 5"
MAX. RUN 14"
MIN. RUN 10"
MAX TREAD 14"
MIN TREAD 11"